

SCIENTIFIC AMERICAN


[Entered at the Post Office of New York, N. Y., as Second Class Matter. Copyright, 1901, by Munn & Co.]

A WEEKLY JOURNAL OF PRACTICAL INFORMATION, ART, SCIENCE, MECHANICS, CHEMISTRY, AND MANUFACTURES.


Vol. LXXXIV.—No. 8.
ESTABLISHED 1845.

NEW YORK, FEBRUARY 23, 1901.


\$2.00 A YEAR.
8 CENTS A COPY.




Throwing Silk—Spinning and Doubling Machines.




Winding.




Setting a Warp for Broad Silk.



Cleaning a Harness.



A Ribbon Loom.



A Broad Silk Loom.

THE SILK INDUSTRY.—[See page 118.]

Scientific American.

ESTABLISHED 1845

MUNN & CO., - - - EDITORS AND PROPRIETORS.

PUBLISHED WEEKLY AT

No. 361 BROADWAY, - - NEW YORK.

TERMS TO SUBSCRIBERS

One copy, one year, for the United States, Canada, or Mexico \$3.00
One copy, one year, to any foreign country, postage prepaid. \$3 10s. 5d. 4.00

THE SCIENTIFIC AMERICAN PUBLICATIONS.

Scientific American (Established 1845).....\$3.00 a year.
Scientific American Supplement (Established 1876)..... 3.00
Scientific American Building Edition (Established 1885)..... 2.50
Scientific American Export Edition (Established 1870)..... 3.00

The combined subscription rates and rates to foreign countries will be furnished upon application.

Remit by postal or express money order, or by bank draft or check.

MUNN & CO., 361 Broadway, corner Franklin Street, New York.

NEW YORK, SATURDAY, FEBRUARY 23, 1901.

The Editor is always glad to receive for examination illustrated articles on subjects of timely interest. If the photographs are sharp, the articles short, and the facts authentic, the contributions will receive special attention. Accepted articles will be paid for at regular space rates.

EAST RIVER RAPID TRANSIT TUNNEL.

The Rapid Transit Commission, having approved its engineers' plans for the extension of the subway system beneath the East River to Brooklyn, is now seeking the necessary powers to proceed with the construction. We trust that the required authority will be secured, and with the least possible delay. The present Rapid Transit scheme terminates in a four-track loop beneath City Hall Park. The proposed extension, the estimated cost of which is about \$8,000,000, will reach from City Hall Park, New York, to the Borough Hall, Flatbush Avenue, and the Long Island Railroad depot in Brooklyn.

The new structure will consist of a two track subway which will extend from the City Hall, beneath Broadway to Pine Street, where it will change into two two-track structures, separated by a partition wall, each of which will contain an up and a down track. At Battery Park one of the two-track structures will swing into a return loop terminal. The other structure will turn to the left, and on a descending grade will connect with two 15-foot parallel cast iron tubes, by which the tracks will be carried beneath the East River. On the New York and Brooklyn sides of the river, the tracks will have an elevation of 66 feet and 68 feet below mean high water. They will descend from either side to a sump below the center of the river, where the elevation will be 91 feet below mean high water, the respective levels being 31, 47 and 32 feet below the bottom of the river. The tubes will be carried on the Brooklyn side beneath Joralemon Street to the Borough Hall, where they will connect with two subways, one of which will swing into a terminal loop encircling the Borough Hall, the other extending below Fulton Street. Above the terminal loop of the tunnel tubes already mentioned as encircling the Borough Hall, there will be another loop which, after making the circuit of the Hall, will also run up Fulton Street, ultimately connecting with the single track from the lower loop, and forming a two-track structure which will extend to Flatbush Avenue, and from there to the Long Island Railroad.

The sum of \$8,000,000, which this extension is to cost, might seem, at first thought, to be a heavy addition to the cost of an enterprise for which a sum of over \$35,000,000 has already been authorized; but we must remember, first, that the efficiency of the Manhattan Island subway will be vastly increased by this extension; and, secondly, that all provisions for rapid transit in a city which grows as rapidly as New York, must be built with an eye to the enormous traffic requirements of the future.

SIR WILLIAM WHITE AND THE NEW ROYAL YACHT.

A notable instance of the celerity with which a host of detractors will rush into print in the effort to ruin what they consider to be the shaken reputation of a truly great man is seen in the case of Sir William White, the Chief Constructor of the British navy. In all the world there is not to be found a naval architect who is responsible for such a vast amount of work as is carried out under the Chief Naval Constructor of Great Britain, and it must of necessity follow that, in a position which entails so much routine official work, he is unable to do more than lay down the broad features of new designs, and must leave the details to his subordinates. It seems that in the construction of the royal yacht, the distribution of weights was such at the time of her launch that she proved to be unstable. The error was traced to one of the staff, and subsequent reconstruction in the way of cutting down the topmasts, funnels, etc., so far corrected the instability of the vessel that at her recent trials, in which she made about 21 knots an hour, she proved to be an excellent seaboat in all kinds of weather.

The attack upon Sir William White was indignantly resented in naval circles, and nowhere more so than in the United States navy. Several of our naval constructors, including Constructor Bowles, the coming Chief Constructor, were at one time students of Sir William White in England, and their strong testimony to his abilities has been indorsed by Charles Cramp, president of the well-known shipbuilding firm of that name. As a matter of fact, the modern navy of Great Britain, dating from the era of the Naval Defense Act, is entirely of his designing, and the correctness of his theories is proved by the fact that the type of ship to which he has clung steadily, with few variations, for the past fifteen years bids fair, at least in its general features, to become general throughout the world.

TESLA'S WIRELESS TELEGRAPHY.

Long distance wireless telegraphy, if we may believe the current story of its latest developments, is about to take an enormous stride both in its reach and its rapidity, for we are shortly to be in possession of a means of wireless telegraphic communication across the Atlantic, by which we can send messages at considerably greater speed than is possible by the present cable. The feat is to be accomplished by the assistance of that "oscillator" with which the name of Nicola Tesla is so well identified. We are, all of us, fairly well familiar with the Marconi system in which Hertzian waves are utilized, the transmission of currents being aerial, or to speak more correctly ethereal. Mr. Tesla, however, manipulates his recently discovered "stationary electrical waves in the earth" by setting up "vibratory currents which can be transmitted through the terrestrial globe, just as through a wire, to the greatest distances."

According to public reports, Mr. Tesla during the past year or so has been devoting his time chiefly to the improvement of his generator and receiver. He claims to have so far perfected the system that by means of proper "tuning" he can direct his messages infallibly to any particular receiver. It seems that the primary purpose of his recent Pike's Peak experiments was a series of elaborate tests, the result of which satisfied Mr. Tesla that when a suitable plant is built, he can establish wireless electrical communication between the old and the new world. The system, as described in interviews with the author, involves the production of electrical vibrations of enormous frequency, a transmitter which receives the current, intensifies it, and sends it to the earth, through which it flows in every direction. A receiver which is adjusted so that its vibrations are in tune with those of the transmitter is set up, say in London, Paris or Berlin, picks up the vibrations, and intensifies them so that they become decipherable at the receiving station. These electrical vibrations are recoverable at any spot on the surface of the globe, provided that the Tesla receiver be at hand to pick them up, and intensify them to a point at which they may be read.

HIGH-SPEED PASSENGER STEAMERS ON THE HUDSON

It is somewhat surprising, in view of the excellent facilities for a rapid steamer service afforded by the Hudson River, and the inducement which is offered by the existence of many populous residential suburbs along the shores of the river, that there has been no attempt as yet to manipulate such a line for the benefit of suburban residents. It was only at the close of last year that preliminary steps were taken looking to the provision of a service of this kind, and the scheme has now reached a stage of its development at which some facts regarding the vessels which are to be employed will be of interest. There will be three twin-screw vessels, built from designs by Mosher upon the lines of the remarkable type of craft with which his name is identified. They will be 130 feet in length, 15 feet in beam, with a depth of 7 feet, and an extreme draft of 4½ feet. They will have two twin-screw, quadruple-expansion engines of 4,000 horse power, and the displacement, with an average load on board, will be about 100 tons. There will be a large general saloon, and a smoking saloon, and a seating capacity for 250 passengers. The lines of the boats will be similar to those of the "Ellide," which is credited with a speed of 34¾ knots an hour on the measured mile; and while these steamers will be capable, when the engines are run at their full power, of making an equal or even greater speed than this, the present arrangements are to run them at a speed which under normal circumstances will enable them to make the trip from Nyack to 22d Street, New York, in one hour. A steamer will leave every hour from six o'clock in the morning to eleven o'clock at night, and calls will be made at Rector Street, 22d Street, Yonkers, Dobbs Ferry, Tarrytown and Nyack. The landings will be made at the ends of the piers and there will be special provision made to allow a clear course for the steamers in approaching and leaving the docks. We think it is more than likely that such a service will prove extremely

popular during at least six months of the year, and its successful maintenance will mark a very important step in the development of high speed travel by water.

SMOKELESS POWDER AND GUN EROSION.

The Board of Ordnance of the navy is to be congratulated on the excellent results obtained with the multi-perforated smokeless powder, the perfecting of which has involved a great amount of investigation and experiment. The advantages of smokeless powder are well known to the public; but it is not so well understood, perhaps, that these advantages, in the case of some of the best-known smokeless powders, are largely offset by certain serious defects, chief among which is their destructive action upon the interior surface of the gun, which is shown in a pitting or eating away of the bore. The direct result of this erosion is that, the obturation being imperfect, the gases escape past the shell, and there is a consequent falling off of the muzzle velocity below that which theoretically should be produced by a given charge of powder. This erosion is most marked in the case of smokeless powders that contain a large percentage of nitroglycerine, the well-known cordite which contains over 58 per cent of this explosive being, perhaps, the chief offender in this respect. The temptation to include a large percentage of nitroglycerine is due to its enormous energy; but it has always been recognized that if a powder could be produced that contained a minimum of nitroglycerine, and still possessed high ballistic qualities, it would be an ideal powder. It is satisfactory to know that the ordnance officers both of the United States army and navy have developed powders which are so far superior to cordite, that the army smokeless powder contains only 25 per cent of nitroglycerine, and the navy powder none at all, the latter being an all-gun-cotton product.

It is with this powder that the Board of Ordnance has secured the remarkable ballistic results which, from time to time, have been chronicled in the SCIENTIFIC AMERICAN. Thus, the new 12-inch naval rifle has shown a velocity of 2,854 feet per second, while velocities of 3,000 foot seconds and over have been obtained with the 6-inch, 4-inch and 3-inch 50 caliber guns, and in every case these high velocities have been obtained without exceeding the designed chamber pressure of 17 tons to the square inch, and, what is equally important, without any sacrifice of the mass of the projectile.

So much for proving ground results. Can they be sustained in regular service; or will there be, as in the case of the naval guns of at least one foreign power, a gradual falling off in velocity, due to erosion and enlargement of the bore? It is with considerable satisfaction that the Ordnance Bureau is able to certify that no such deterioration will result from the prolonged use of its new powder, since a 4-inch rapid fire gun at the Indian Head Proving Ground has been fired 661 times, and a 5-inch gun 636 times with the smokeless powder, without causing sufficient wear to be detected by micrometer measurement.

Another defect to which smokeless powders are liable is that when they are in storage, or in the magazine, for a considerable length of time, they are liable to undergo a chemical action which results in a great falling off of energy. Powders that depreciate with age give unreliable results in service, since it can never be determined just exactly how the gun sights should be adjusted. Should they be adjusted to suit the full velocity of the powder when that velocity is actually one or two hundred feet per second below the designed velocity, the shell will fall proportionately short of the object. Hence, stability is a feature which is second only in importance to that of erosion, and it is gratifying to learn from the Department that our navy powder has proved to be thoroughly stable, a sample of powder which had been in the magazine for two years having shown at a recent test that there had not been the least loss of its ballistic qualities, nor any evidence of chemical alteration.

PRIZES FOR INVENTIONS A LEGITIMATE ENCOURAGEMENT

The closing year of the nineteenth century was a remarkable one in the field of invention, not only as regards the number of patents issued, but for the remarkable inventive ability displayed. It is gratifying to note the increase in the esteem in which inventors are being held, and the substantial rewards which crowned many of their efforts. They can reap not only the full benefits to be derived from their inventions, but they can also compete for the remarkable series of prizes which have been offered by associations and individuals in the hope of improving our economic condition. The great prizes of 1900 were the Pollak prize for life-saving devices, which was \$20,000; the prize offered for labor-saving machinery for the sugar business, made by the Hawaiian Planters' Association, the amount being \$6,500, and a number of prizes of smaller value. There is every indication that the year 1901 will be even more fruitful in liberal offers for inventions than the year which preceded it. Only \$2,000 of

the Pollak prize has been adjudged to those who exhibited their devices; consequently there is a large sum to be awarded in September, 1901. It has not been decided as yet to whom the prize of \$6,500 for improved sugar machinery will be given. During 1901 the Nobel prizes will be awarded, and in three of them the inventor may find his opportunity. One prize will be for the invention or discovery made in the domain of physical science, another prize in chemistry, and a third in physiology and medicine. The value of each of these prizes is very large, being \$80,400. It should be remembered that in none of these cases does the inventor part with any of his rights, and his receiving a prize does not interfere in any way with the material reward of the inventor. The recent success of Prof. Pupin in selling an invention for nearly \$500,000 is fresh in the memory of all.

It is becoming quite customary for societies and associations to offer prizes for what might be termed minor discoveries. For instance, the chief topics of discussion of the Chemical Congress, at the recent meeting held at Hanover, was a substitute for benzene, and last autumn the subject came up once more at the meeting at Cassel, and it was decided to offer a premium of \$250 for an effective substitute for benzene, or for means for rendering it less dangerous, the objectionable points about benzene being its inflammability and volatility and the danger of poisoning the atmosphere.

At first sight it might seem as though this was a very small prize for a society to offer, but, as it has already been stated, the inventor does not, by accepting a prize of this nature, cede any of his rights, which, in the case of a substitute for benzene, would undoubtedly bring the inventor large wealth. The Bressa prize of \$1,920 is offered by the Académie Royale des Sciences de Turin, and the competition is open to savants and inventors of all nations for the most important discovery in the arts and sciences during the period 1897-1900. The aggregate of prizes offered is by no means inconsiderable, and tends to stimulate invention in a healthy manner.

ARE YOU ABOUT TO BUILD?

The Building Edition of the SCIENTIFIC AMERICAN occupies in its field the same important position held by the parent paper in its own sphere of activity. The scope of the Building Edition has been enlarged by the introduction of many new and valuable features. No periodical in the United States can claim more distinction as regards its mechanical execution than this beautiful monthly magazine, with its fine views of exteriors and attractive interiors. The policy of showing only executed work is strictly adhered to, thus differentiating it from many of its contemporaries. The illustrations show how the house actually looks, the plans show how it is arranged, the description of the plates tell how it is built, who owns it, who is the architect, and who are the contractors, and when attainable, its cost. This information is all valuable to those about to build, as well as those who are interested in the subject from a professional and financial point of view. There are many interiors and examples of home decoration, showing what can be accomplished on various scales of expenditure. Other plates are devoted to interesting subjects at home and abroad, such as public buildings, churches, libraries, fine iron-work, stables, etc. Groups of cozy corners, doors, windows and other similar features will be published throughout the year.

The literary contents comprise a number of new features which will enhance the value of the magazine many fold. "Monthly Comment" is devoted to current events. The editorials deal in a practical manner with the problems which confront the architect, contractor or owner in the design, execution or improvement of the house. As wide a range of the subjects as possible is given. "Interviews With Architects" forms a new feature of the year, and gives the ripe experience of men standing high in their profession in a most interesting manner. "New Books" will deal with the latest publications, and the reviews will be discriminating. The Correspondence column will tend to keep the Editor and reader in close touch. Any question relating to subjects of architecture, building, sanitary science, etc., will be answered and a cordial interchange of views between readers encouraged. "New Building Patents" will contain a digest of patents relating to building and sanitary science. Each month a considerable space is devoted to a summary of current articles within the purview of the paper. This digest will consist of condensations of long articles relating to building and also shorter notes, and the field covered will be a wide one. On the whole, the Building Edition merits the warm support of every one directly or indirectly interested in architecture or building.

ZENOBE T. GRAMME.

Zénohe T. Gramme died near Paris on January 20, and in his death electrical science has suffered a great loss, as he was the inventor of the Gramme ring, which

made the modern dynamo possible. He was born in 1836 in Belgium and in early life was a carpenter. He became interested in electrical construction, and in 1870 he improved on the toothed-ring armature of Pacinotti and devised the uniformly wound ring armature machine with which his name has ever since been connected. His dynamo, which was exhibited at the Centennial Exposition, 1876, attracted great attention. The commercial success of the machine was rapid. It was the first practical machine in which were combined the features of continuity of commutation, the self-exciting arrangement, good lamination in the armature core, and reasonably good proportions in the magnetic circuit.

OUR BUSINESS AND PERSONAL WANT COLUMN.

We would call the attention of our readers to our Business and Personal Want Column, which will be found on page 108 of our issue of February 16 and page 123 of the present issue. We have taken a new departure in connection with this column, which we think will be fully appreciated by manufacturers throughout the world and by all of our readers who are in search of information which they could not otherwise acquire.

The SCIENTIFIC AMERICAN has now become a center of information for thousands of readers, who apply for information regarding the particular line of manufactured goods in which they are interested—information which they are unable to obtain through the ordinary channels at their command. Our daily mail is flooded with letters inquiring as to who is the manufacturer of this and that article, or of some improvement on a certain machine, which the correspondent would like to buy if he could get into touch with the manufacturer.

We could, of course, give the person inquiring the name and address of one or two manufacturers in the line requested, but it occurred to us that it was only fair to our readers and enterprising manufacturers that we should endeavor to ascertain for the party inquiring the name and address of every manufacturer that we possibly could in the line desired, thus giving him a wide field for choice, and opening the way for pushing manufacturers to compete with some chance of success.

It will be seen at a glance that this column will open up a new and important field to manufacturers of all kinds. If they refer weekly to the inquiries in this column they may at any time find therein an inquiry for just the class of goods they deal in or manufacture. A letter to us, preferably accompanied by their catalogue and giving in brief as much information as is necessary, together with the number of the inquiry, will, in a short while, put them in immediate touch with the party who desires to buy the goods in question. We, in fact, act as a clearing house between the persons desiring information and the manufacturers ready to fill their wants.

We hope that our efforts will be appreciated to the extent that all manufacturers in the lines inquired for will assist us by weekly replying to these inquiries, as it may be the means of opening a greater field of trade than is now possible.

ZODIACAL LIGHT.

M. Leo Brenner has lately given an account of the observations on the zodiacal light which he has made at the Observatory of Manora (Austria). Very few persons have seen this phenomenon; in the northern part of the Continent it is usually quite masked by the lighting of the cities. In the south and in the tropical regions the phenomenon is more striking, but the writer has known many ship captains who have sailed around the globe for many years without having seen the zodiacal light. This phenomenon seems to have been observed only for the last 300 years, and the ancient writers make no mention of it; some have concluded from this fact that the light has only been visible in modern time, but this opinion is difficult to admit. It is generally supposed that the zodiacal light constitutes a clear and distinct phenomenon only in the tropical regions, and Humboldt says that at the Equator, at points of 9,000 to 12,000 feet altitude, it often exceeds in brightness the lightest part of the milky way. However, the author observes that at Lussin, from which he writes, at the sea level, the zodiacal light is generally from four to six times as intense as the milky way and often eight or ten times as bright; this can only be explained in two ways, either that the light is more intense in that region or that the milky way is less brilliant. There the zodiacal light appears at the most favorable times for its visibility, namely from January to March and also in September and October, as a pyramid of light whose base is at the point where the sun has set, while the point traverses the zodiac; at the summit the light is scarcely apparent, but it increases afterward and at a point opposite gives a second cone of light which is called "antizodiacal." This last phenomenon has been the object of observations since 1854, at which time it was examined by Brorsen; however, it was seen in

1803 by Humboldt. The author states that the brightness of the zodiacal light as he saw it was such that often in the main part and up to 40 deg. in height he could not see any of the stars with the naked eye; as to the antizodiacal light, which few observers on the Continent have seen, it appears three times as bright as the milky way, and thus his region seems to be especially favored in this respect. The spectroscope shows that the zodiacal light is reflected solar light, and the polariscope, by which the polarized light is separated from the ordinary rays, confirms this supposition. The green lines of the aurora borealis, sometimes seen in its spectrum, have been shown by Wright to belong not to the zodiacal light, but to aurores which are only observed by the spectroscope. Various theories have been proposed as to the formation of the zodiacal light, but none of these are conclusive.

SCIENCE NOTES.

Michael G. Mulhall, a noted statistician, died recently in London. He forecasted the twelfth American census within 95,000, showing how very precise and accurate statistical science can be in skillful hands.

The United States Weather Bureau was awarded a Grand Prix at the Paris Exposition. Gold medals were also awarded to Prof. C. F. Marvin for instruments, apparatus and appliances, and to Prof. A. J. Henry for cloud photographs. The Weather Bureau will make an extensive exhibit at the Pan-American Exposition.

Major Serpa Pinto, the fourth explorer to cross tropical Africa from sea to sea, died in Portugal a short time ago, his predecessors in the trans-African journey being Livingstone, Cameron, and Stanley. Pinto's journey lasted from November, 1877, when he started from Benguela, to March, 1879, when he arrived at Durban. His book entitled "How I Crossed Africa" is a record of original discovery and of fierce battling with the natives, of hair-breadth escapes, of perils from wild beasts and the depletion of supplies. He was a scientific explorer, which is more than can be said of many pioneers in geographical research.

The American Physical Society met during the holidays in Columbia University. At the morning business meeting the following names of officers for the ensuing year were chosen to be balloted for by the members, the results to be announced at the next meeting: President, Henry A. Rowland, of Johns Hopkins University; Vice-President, A. A. Michelson, of Chicago University; Secretary, Ernest Merritt, of Cornell University; and Treasurer, William Hallock, of Columbia University. The Councilors are Henry Crew, of the Northwestern University, and Edward B. Rosa, of Wesleyan University. After the business meeting six papers bearing on problems in physics were read by as many university professors.

A new species of mountain sheep has been sent from Dawson City to Director Hornaday, of the New York Zoological Society. This species is absolutely new to science, and is so strikingly different as to render its title to independent specific rank beyond question. Director Hornaday has named it the *Ovis Fannini*, in honor of Curator Fannin, of the Provincial Museum of British Columbia. In the Klondike region it is known as a "saddlebacked" or "piebald" sheep. Its head, neck, breast, and abdomen and inside of the fore-legs are of a snow white. The other portions of the body are a brownish gray, giving the animal the appearance of being covered with a gray blanket. There are now 945 members of the society, an increase of 271 during the year. It is desired to increase the membership to 3,000. The total attendance of the year was 525,938, the largest daily attendance being on Decoration Day, 20,134. A motor road will soon be completed in the park, on which the society will operate its own motor carriages for the convenience of the public.

Macaroni is made of hard red wheat from the Black Sea, mixed with Italian wheat grown mainly in the plains around Foggia. This is ground into a coarse flour. The bran and husks are removed, and it is kneaded in hot water until it has the appearance and consistency of dough. It is then placed in a vertical brass cylinder eight or nine inches in diameter, the bottom of which is perforated with holes of various sizes, according to the product desired. The dough is placed in the top of the cylinder and is driven down by hydraulic pressure through the perforated plate, and is cut off by hand in lengths. It is then hung up on canes in the sun to dry. In the case of tubular macaroni and spaghetti, a conical blade is fixed in the middle of the dough to form the tube. This cuts through the dough, and the macaroni issues from the blade with a slit all along its length. This, however, shrinks together at once, and a perfect tube is made. Almost no macaroni is now made by the laborious hand process. There was for a long time a prejudice against machinery, but this has been overcome. The best macaroni comes from Torre dell' Annunziata. Nearly half a million boxes are sent annually to the United States.


POWERFUL NINE-TON DIPPER DREDGE.

There are certain lines of engineering work upon which the American engineer has left his mark so deeply and distinctly that the mere mention of them is suggestive of certain great engineering works in the United States, whose fame has traveled to the ends of the earth. Of this kind are the powerful and ingeniously designed devices for removing material in large masses, of which the work on the Chicago Canal presented some of the earliest and finest examples. The accompanying illustrations represent the latest, and next to the largest, of the dipper dredge types of excavating machine that has been built in this country, the largest being the "Pan-American," which has recently been at work at the Portage Lake Michigan. The dipper dredge is so named because of the action of its excavating bucket, whose motions, as it is plunged into the water and drawn up with its load, is not unlike those of the household implement from which it takes its name. The dredge here illustrated was constructed at Ogdensburg, for use on the Massena Canal, and during the fall it was at work opening up the channel from the St. Lawrence River to the canal proper. The hull measures 121 feet 6 inches in length, by 40 feet in breadth, and its depth at the working end, or bow, is 12 feet 2 inches, and at the stern 10 feet 6 inches. In the construction of the hull care has been taken to give it sufficient longitudinal and transverse strength to withstand the heavy strains to which it is subjected when working in hard material. The sides and ends of the hull proper are stiffened by a continuous wall of wooden trussing, and it is further stiffened by running a deep steel truss entirely around the hull in the plane of the walls of the deck-house. This truss extends from the bottom floor of the dredge to the roof of the deck house, and, of course, adds enormously to the stiffness of the whole structure. In the two corners at the bow are two spuds of colossal dimensions, each consisting of a single stick of Oregon fir measuring 36 inches by 36 inches in section and 55 feet in length. There is another massive spud, also consisting of a single stick of Oregon fir, at the stern. The spuds are raised and lowered, each by means of a single steel wire cable, operated by independent engines. An idea of the power and massiveness of this machine may be judged from the fact that the dipper alone weighs 9¼ tons, and has a capacity of 6 cubic yards at a single lift. A novel feature in the machine is the substitution of a single heavy steel-wire cable for the usual chain-lifting gear for operating the dipper. This cable is 3½ inches in diameter and was specially made for this particular work. It leads direct to the hoisting drum, which is operated through compound gears by a pair of 16 by 18 inch engines. The swinging of the boom is worked by a pair of 11 by 12-inch engines, and the backing is done by another pair of engines of the same dimensions. A separate 8 by 3-inch engine is provided for handling the stern spud. There are also two steel capstans, one on each side of the dredge, each of which has its own independent engine. In addition to the considerable plant as outlined above, there is an engine and direct-connected dynamo for furnishing electric light for the whole dredge. The after part of the deck-house is devoted to the living and dining accommodations for the officers and crew, and two substantial scows, one of which is shown on the starboard side of the dredge, complete the outfit. Our thanks are due to Capt. W. J. Daly for courtesies extended in the preparation of this article.

The Rev. Hannibal Goodwin, well known as an inventor of photographic processes, died recently at Newark, N. J.

Oil Wells in Texas.

The discovery of oil in such abundance near Beaumont, Texas, is somewhat surprising, as the location of the well which has produced such large quantities is nearly 200 miles from the Corsicana field. This would indicate that the oil belt of Texas underlies an extensive territory in the eastern section of the State, representing a field almost as large as that of western Pennsylvania. Oil was first discovered in Texas in May, 1894, in the suburbs of the town of Corsicana while boring an artesian well. Pittsburg

**POWERFUL NINE-TON DIPPER DREDGE FOR THE MASSENA CANAL.**

prospectors became interested, and a number of wells were bored to a depth of 1,000 feet, but none yielded a paying quantity until two years later. Since that time operations have extended over most of Navarro County, in which Corsicana is situated. During the year 1898 development work increased rapidly, and producing wells increased in proportion. During the year producers were drilled as follows: January, including all previous operations, 66 wells; February, 9 producers; March, 23; April, 29; May, 36; June, 24; July, 26; August, 38; September, 28; November, 23; December, 27, making a total of 342 producing wells on January 1, 1899, besides four gas wells, furnishing large quantities of natural gas, which is utilized here for fuel and steam-making purposes.

In 1898 was commenced by J. S. Collinan a refinery with a daily capacity of 1,500 barrels, which began operation early in January, 1899, its capacity since then having been largely increased, as was demanded by the increased output of the field. Month after month the tankage capacity of the refinery was in-

of oil, which will be shipped to that point and refined.

Since January 1, 1899, development work has gone on uninterruptedly until the number of producing wells in this field is about 600, besides 17 gas wells. The total output of the 600 wells is 4,000 barrels a day. The refinery is not able to refine the entire product, and large quantities of crude oil are shipped to Mexico, where it is refined by a company in a manner connected with the company in Texas. There is a low duty on the crude article, which admits of

it being shipped and sold. The residuum of the oil is used in the mills and factories for fuel, and is sold to them by the refinery at 60 cents per barrel after all the illuminant has been abstracted from it. The consumption of this residuum, however, is not so large as the supply, and trainloads of it are shipped weekly to Sabine Pass, at which point it is loaded on steamships and shipped North, where the by-products are utilized for the manufacture of various articles of commerce.

In addition to the oil field in Corsicana, a new field has recently been opened near Powell, eight miles east, in which, at a depth of about 400 feet, oil of the lubricating variety has been found in paying quantities. One well in this field for nearly a week

yielded 100 barrels a day, then subsided to a "pumper," with an output of 10 or 12 barrels a day—about the average of wells in that field. There is no market for this lubricating oil yet, but a pipe line will be built to the field in order to get it on the market.

Development work is still being pushed in both fields, and each month furnishes on an average of 25 producing wells, while the wells abandoned average about 9 per month.


Analyses made by various experts show that the Texas oil furnished the following distillates: One-half liter, or about one-half pint, was subjected to distillation, and the following fractions obtained at the respective temperatures expressed in degrees of the Centigrade scale: Began to boil at 80 degrees; between 80 degrees and 90 degrees gave off 16.4 per cent of its volume; between 90 degrees and 110 degrees gave off 7.8 per cent; between 110 and 140 degrees, 10.4 per cent; between 140 and 170 degrees, 9.2 per cent; between 170 and 200 degrees, 3.6 per cent; between 200 degrees and 280 degrees, 16 per cent; between 280 and 305 degrees, 11.2 per cent; above 305 degrees, 15.8 per cent, making the total volatile matter about 90 per cent, leaving a coke residuum of about 10 per cent. The Corsicana oil compares favorably with the Pennsylvania product, which generally yields in product 60 to 75 per cent of burning oil of first and second quality.

Russian Sugar Manufacture.

In our issue of November 3 we published a short notice entitled "How Russia Corners Sugar." We now find that in Russia every manufacturer is required by law to export a fixed amount of his product on which he receives a rebate of one ruble 85 kopeks per pood, excise tax. There are 280 manufacturers of sugar in Russia, but only 20 of them are refiners; they supply the home market, the refined article being too hard for other countries, it being the habit of the peasant class, the

largest consumers of sugar, to hold a lump in their mouths while drinking tea.

Russian sugar is said to be 99 per cent pure, and for that reason the best in the world. Russian sugar stocks pay from 15 per cent to 50 per cent dividends annually. There is some demand for Russian sugar in the United States, and some Russian sugar is reaching this market. Two of the largest refineries in Russia were destroyed by fire last May and the owners were delayed in rebuilding by the scarcity of money and finally decided to rebuild with a decreased capacity.

**HOISTING ENGINES FOR THE DIPPER.**

creased, until now there are between thirty and forty tanks holding from 16,000 barrels to 36,000 barrels each, while others are being added as production increases. The refinery buildings, tanks, machinery, and pipe lines represent an expenditure of about \$300,000. Prices since the first 100,000-barrel contract was made have gone up as high as \$1.11 per barrel, at which point a decline began and continued until oil sold at 67 cents per barrel, which caused a movement to build an independent refinery and pipe line. A small refinery was built at Houston, 250 miles south, and the company has contracted for 100,000 barrels

PETROLEUM AS AN ILLUMINANT FOR BUOYS.

We have frequently advocated in the columns of the *SCIENTIFIC AMERICAN* the more general utilization of petroleum, both as an illuminant and a fuel, mainly because of its cheapness, abundant supply, and efficiency. One of the latest applications of this oil is that for the illumination of buoys, and it is the invention of Mr. James Richardson Wigham, the well-known lighthouse engineer of Dublin, Ireland.

Although the adequate illumination of rocks and shoals by buoys is indispensable for the safe navigation of rivers, estuaries and harbors, it is not imperative that the light cast from the buoys should be of very powerful illuminating intensity. Indeed, it is very seldom that the visibility of their rays is desired from a range exceeding five or six miles. But, on the other hand, occasionally buoys have to be placed in isolated positions, where it is impossible to erect lighthouses, and, owing to the difficulty of access thereto, it is essential that they should continue to burn brilliantly, without any attention, for several weeks or even months. Compressed oil gas is the illuminant generally employed for this purpose, since, although it is more expensive than oil, it possesses none of the drawbacks inherent to the latter. The principle expense incurred by the utilization of oil gas is the installation of the special gas-making establishment on shore. By the use of petroleum, however, all such expense is averted, because it is only necessary to convey the oil to the buoy to replenish the lamp reservoir.

The great disadvantage which has always militated against the satisfactory application of oil is the manipulation of the wick. In a short time after the ignition of the lamp the wick becomes so charred that the capillary attraction which brings the oil to the point of combustion is obstructed, and the light goes out. An attempt was made to overcome this drawback by the construction of a carbonized wick, but, although it lasted longer than the ordinary wick, in a few days the deposit from the oil was sufficient to extinguish the light.

The inventor carried out numerous experiments with a view to overcome this obstacle by causing the wick to move automatically as it was consumed, so that the same part of it would not be constantly exposed to the action of the heat of the combustion, thus securing a constant brilliant light. But this was an impossible task under the existing circumstances where the wick in the lamp is placed perpendicular to the level of the oil in the oil container, since it could not be readily made to alter its position automatically as its combustion proceeded. Mr. Wigham, therefore, conceived the ingenious plan of passing the wick over a roller, thus burning it horizontally, so that the light was obtained from the side and not from the end of the wick.

The burner he has invented is surmounted by a combustion cone, and surrounded by lenticular apparatus. One end of the wick, *E* (Fig. 3), is conveyed up through an oil tight copper tube with holes in its sides, and passes over a roller, *F* (Fig. 3), at the burner, *C* (Fig. 2). The other end is brought down through a tube standing above the level of the oil in the lamp and soldered or secured at the lower end. A circular float, *A* (Fig. 2), is placed in a copper cylinder fixed to the bottom of the lamp and filled with oil. When the lamp is first lighted this float is at the top of the cylinder, and is attached by means of hooks or loops to the wick. The oil in the cylinder is caused to drop slowly out of it through a valve, *D* (Fig. 2), of peculiar construction, supplied with a cotton core, at such speed as may be necessary. The oil thus descends into the receiver, bringing with it the float and the wick which is attached to it. When, at the end of one month, or any such other period as may be desired, it is necessary to replenish the lamp with oil, the cylinder is refilled, as is also the reservoir under the lamp.

It is necessary to fix the lamp upon swivels or gimbals, so that, however great may be the motion of the sea, the lamp always maintains practically a level position. Divisions are fixed in the

oil reservoir by which, should it for a moment be brought out of level by the motion of the sea, the oil is prevented from flooding the wick during the passing of the wave, after which its proper level is again maintained.

The cost of lighting buoys by mineral oil is very trifling, the consumption being about half a gallon of oil every twenty-four hours. In connection with the buoys at present employed in Belfast Harbor, which are lighted





Fig. 2.

Fig. 3.

SECTIONAL ELEVATIONS OF LAMP AND BURNER.



PETROLEUM BUOY.

by this means, this amounts to an expenditure of about 6 cents per twenty-four hours. This cost may be decreased if the oil, which constantly drips from the cylinder of the lamp, is collected in a portable vessel instead of falling upon the water, to 2 cents per twenty-four hours. The oil which apparently runs to waste, however, performs a valuable function, for it serves to calm the sea in the vicinity of the buoy.

This system of petroleum illumination of buoys has been used with conspicuous success in many of the harbors and estuaries of Ireland. In some cases the lamps only receive attention once in three months, which is sufficient testimony to their efficiency. The numerous advantages of the oil over the compressed gas are obvious, and the action of the lamp is so simple as to be of easy application.

THE ORCHESTRA-MAN OF THE EXPOSITION.

There was much music to be heard at the Exposition of 1900, but the most original was, without any doubt, that played by M. Malboech in the vicinity of

the Gallery of Machines. This extraordinary man is capable of playing as many as thirteen instruments—the piano, cornet à piston, clarinet, violin, a chime of forty bells, the bass drum, cymbals, triangles, two kettle drums, tabor, and castanets.

By means of his hands he plays either the piano or the clarinet and piano at the same time, but more generally the cornet à piston and piano. The left hand, used for this latter instrument, actuates the chimes also. The secondary instruments are played through the pressure of the feet upon pedals.

These multiple occupations do not prevent the artist, while playing the cornet, from smoking his pipe. This is a fact that it is impossible to see accomplished every day. Our musician correctly executes pieces that are often difficult, and when a person closes his eyes he would be willing to affirm that he was present at a concert given by a dozen persons, so great is the volume of sound produced. The execution is sometimes fantastical, as, for example, when a gun is fired to terminate certain scores à la Berlioz or à la Wagner.

Malboech himself superintended the installation of his orchestra and arranged the different parts of it.

Although the artist, who is a native of Holland, is but forty years of age, he has traveled over nearly the entire world. He announces in his circulars that he offers \$2,000 to any one who will succeed in imitating him, and styles himself "the greatest artist in the world."—*La Nature*.

Therapeutic Action of Light.

Dr. P. Garnault has lately read a paper before the Académie des Sciences dealing with the therapeutic action of light, and mentions a number of cases in which he has used this treatment with success. His attention was first called to the subject by M. Trouvé, who was among the first to bring out this action of light; in 1893 he observed that a workman afflicted with rheumatism was completely cured after having remained for forty-eight hours in the vicinity of a very intense arc light used for an electric fountain. Since then it has been observed that in works where electric soldering is carried on, this being accompanied by great luminous intensity, the workmen cease to be affected with gout or rheumatism. In the present experiments Dr. Garnault uses apparatus which has been specially constructed for the purpose by M. Trouvé. The experiments were confined to the effects of local action of light, and there seems to be no doubt that the results are due to the light radiations and not to other causes. A lamp of 50 candle power provided with a silvered parabolic reflector was applied in eight cases of muscular or

articular rheumatism of average gravity and several years' standing, and in all these cases a very marked improvement was obtained at the end of three to twelve operations, and not followed by a relapse. Chronic catarrh of the nose may be also treated with success by the application of light accompanied by vibratory massage. The treatment was also applied in cases of deafness, accompanied or not by humming noises in the ear; the apparatus used consisted of two ten-volt lamps provided with reflectors and applied to each ear by a curved spring passing around the head; in some cases the action of heat was eliminated by placing alum screens in front of the lamps. In three such cases a marked diminution of the humming noises and an improvement of the hearing; other cases without the use of the alum screen were so successful. The most complete observation was made upon a person thirty years of age who had undergone, the year before, an operation in which the tympanum and small bones of one ear had been removed; on the operated side the intensity of the humming noises had been greatly reduced, but on the other they were very marked; these were made to disappear by a series of applications of light. They reappeared after a severe cold contracted by the patient, but were again made to disappear by a second treatment. In twelve cases of deafness the application of light brought about good results. Dr. Garnault has also used the treatment in other cases, and is convinced that the luminous rays may be



MALBOECH THE ORCHESTRA-MAN.

used in certain affections as a local agent to great advantage, and that the results obtained are certainly due to its specific action.

SILK MANUFACTURE.

Although silk is a substance that is produced by several varieties of insects, it has come to be almost exclusively associated in the public mind with the product of a particular variety of caterpillar, which is popularly known as the silkworm, and by the entomologists as the larva of *Bombyx mori*, or the mulberry-feeding moth. The eggs of the silkworm are hatched by artificial means, and are exceedingly small, weighing about a hundred to the grain. It is customary to place pieces of finely punctured paper above the trays in which the eggs are being hatched. As soon as the worms break through the shell they creep through the holes in the paper in their endeavor to get to the light, and in doing so scrape off the pieces of shell which may adhere to their bodies. They are reared in rooms where particular care is taken that an abundance of fresh air and light are present, and where the temperature may be kept at an even point. The worms are voracious feeders and begin to increase rapidly in size from the day they are hatched. As a rule the silkworm moults four times during its life; usually about the sixth, tenth, fifteenth, and twenty-third days after being hatched. As soon as the caterpillars have reached their full growth they climb the twigs and small branches which have been prepared for them, and begin the spinning of their cocoons. The silk glands of the worm consist of two sacks running along the sides of the body, with a common opening on the under lip of the worm. In the process of spinning its cocoon the silkworm ejects from both glands a line of extremely fine thread. The two filaments from each gland are laid side by side and are held together by an adhesive secretion from the worm. The cocoons are either deep yellow, white, or light green in color, and ovoid in shape. Their average length is from an inch to an inch and a half, and they are from half an inch to an inch in diameter. The cocoon consists of an exterior made up of broken and straggling filaments, while the interior layers are densely glued together into a mass which is not unlike parchment, and which is impossible to unwind except by moistening.

The manufacture of silk may be broadly divided under the heads of reel silk manufacture and the manufacture of spun or waste silk. The first method has to do with continuous fibers thousands of yards in length. In the spun silk industry the raw materials are worked up by methods similar to those used in the case of cotton and other fibrous materials.

The first operation is to produce the "raw silk" of commerce. The cocoons are placed in warm water for the purpose of softening the natural gum with which the filaments of the cocoon were fastened at the time it was spun. From six to ten of the cocoons are put in a bath, and as soon as they are properly softened the threads of each are caught up by an attendant on a fine brush, and passed through an eyelet to a reel, upon which they are wound.

The reel consists of a light, wooden, revolving frame, which winds the silk into what are known as skeins, and it is in this form that the silk is usually received at the silk mills.

The first thing to be done with the skeins after they are taken from the bales is to soak them thoroughly in cold water. The raw silk is too fine and delicate for textile manipulation, and has to be doubled and twisted to give it the necessary body and strength. To this end the skeins of raw silk are placed on light wheels, known as "shifts," from which the silk is wound onto spools; then two spools of silk are run together and doubled and afterward twisted, some of the twisting machines, however, performing the doubling and twisting in one operation. The twisted silk is then wound onto rectangular frames, known as creels or reels, and at the same time is measured off into lengths of from 10,000 to 15,000 yards, the silk now being once more in the form of skeins. It is then taken from the creels and rolled up into hanks, ready for dyeing.

After the silk has been dyed it is returned in skeins, which are slipped on over a set of what are known as "soft silk" winders, from which it is wound onto spools once more. It is then taken to the warping department, where the spools are placed upon tables which may carry from 110 up to as many as 600 pegs. In the hand-warping machines there will be from 100 to 120 spools on a table, while the power-warping machines will carry from 300 to 600 spools. The operator gathers up the ends of silk on each spool and runs the threads onto the frames in the mill, the threads in this case being wound parallel. From 100 to 4,000 threads are run off on warping spools, which are technically known as "beams"—round cyl-


inders of wood or iron which are 6 or 7 inches in diameter, and of a width which varies from 4 inches to 36 inches, according to the character of the fabric of which the thread is to form the warp.

The beams are then carried to the looms, where the threads are first led through a "harness," and then passed through a steel "reed" or comb, there being from two to fourteen threads in one "dent," according to the quality of the goods. The harness consists of a series of top and bottom slats known as "shafts," each pair of which is connected by a number of parallel vertical threads at the center of each of which is a small brass eyelet through which the silk threads are passed. Several of these sets are arranged vertically behind each other in the loom, and each harness with its set of threads is raised in turn between each passage of the shuttle through the warp. Each harness thus serves to lift a different set of threads for the passage of the shuttle; and it is by the proper adjustment of the vertical motions of the harness to the strokes of the shuttle that the nature of the weave of the goods is determined. The woven fabric is then taken to the packing room, where all knots, dirt, and stains are removed.

The goods are now taken to the finishing department, where it is put through a variety of operations which would necessitate another article to adequately describe them. Among other operations is that of singeing, to take off any rough nap that may be left on the goods, and sprinkling or sponging with a preparation of wax and gelatine, a process which is not unlike that of starching in laundry work. The final gloss or finish is secured by calendering, in which the fabric is run between a series of superimposed steel rolls, where it is ironed out and the fine glossy finish is secured. The goods are then either folded or wrapped on blocks ready for the market.

Projects for Utilizing the Hydraulic Power of the Rhone.

A number of projects are under consideration for



THE SILKWORM, FROM EGG TO FULL-GROWN LARVA.

1. Eggs on paper. 2. Newly-hatched worms feeding on mulberry leaves. 3. Silkworms at first moult. 4. Second moult. 5. Third moult. 6. Full-grown, ready to spin.

utilizing the hydraulic power of the Rhone, and there is no doubt that before long a number of plants will be established at different points, and it is expected that more than 200,000 horse power at a maximum, or 100,000 at a minimum, will be obtained. Three important projects have been planned, each by a syndicate of manufacturers; these plants will all be installed upon that portion of the Rhone which lies between Pymont and Fort de l'Ecluse, near the Swiss frontier. In this region the river has many rapids and falls; for instance, over a distance of only 12 miles the difference of level is about 200 feet. On the other hand, since the city of Geneva, using Lake Lemman as a reservoir, has regularized the supply at periods of low water, as much as 160 cubic yards per second may be counted upon, below the junction of the Rhone and the Arve; from this it follows that over this stretch of 12 miles about 100,000 horse power may be obtained at low water. During 9 or 10 months, the maximum period, as much as 200,000 horse power is obtained. A hydraulic plant has already been installed in this region by an Anglo-Swiss company, who use about 10,000 horse power. The three projects in consideration have been made by syndicates of French manufacturers, who are only waiting until the formalities have been completed before commencing work. The plans have all been drawn up for some time past, and the land has been purchased. The first of these projects is that of Malpertuis. At 2½ miles below Bellegarde the river falls at a height of 30 to 35 feet at the "Passe de Malpertuis." The river here flows between two perpendicular banks only 160 feet apart. According to this project, a dam will be constructed at a point above the fall, and a part of the water, 160 cubic yards per second, will be taken off by a tunnel

of 60 square yards section and 1.2 miles long; a total fall of 51 to 55 feet will thus be utilized, from which a force of 25,000 horse power will be obtained at low water. The second project is that of the "Boucle de Rhone." A dam will be placed at Les Andelieres, near Bellegarde; here the banks are somewhat wider, and the dam will cover 100 feet and have 20 to 22 feet height. A tunnel just above the dam will take off 160 cubic yards per second (80 to 90 at low water). The tunnel will be somewhat shorter than the preceding, and will end at Essertoux. A total fall of 80 to 85 feet will thus be obtained, giving 24,000 to 25,000 horse power, besides 5,000 to 6,000 horse power taken directly by a small hydraulic plant installed beside the dam on the right bank; this gives a total of 30,000 horse power. The third project is that of the Pont de Gresin. At this point, about 8 miles from the Swiss frontier, the river flows in a narrow gorge only 80 feet wide, and is here 25 feet deep, on an average. This point is near the railroad from Lyons to Geneva, and is thus a good locality for establishing industries; a branch line of 2 miles would connect it to the railroad. The fall of water obtained by a dam at this point will be 65 feet, with an output of 150 cubic yards per second during low water, and double this amount for the rest of the year. A minimum of 30,000 horse power may thus be counted on. The plant will include a dam with movable gates, a hydraulic plant with turbines and dynamos, and a system of canals for the discharge of water. The dam will form a vast lake, or water reservoir, and the water will be taken directly into the station by conduits passing through the walls; after passing the turbines it will be discharged into the river below the dam. The generating plant will contain fifteen turbine-dynamo groups of 2,000 horse power each; the turbines with horizontal shaft will be coupled directly to polyphase alternators; a set of smaller turbines will drive the exciting dynamos, and the station will have the necessary switchboards and appliances. It is probable that within three years these projects will have been completed, and the Bellegarde region will possess a total of 100,000 horse power at low water, and 200,000 during nine or ten months of the year. This will be utilized either on the spot for the manufacture of electro-chemical or metallurgical products—such as carbide of calcium, vanadium, carbonates of sodium or potassium, aluminium, etc.—or for the supply of energy over a radius of 80 to 90 miles, following the example of the Niagara plant.

A Prize for Communication With Other Planets.

The sum of 100,000 francs was bequeathed to the French Academy of Sciences in 1891 to be awarded to the first person who would be successful in communicating with another world. The Academy at first did not care to accept such a curious bequest, but finally it did so in the following words: "Madame Veuve Guzman, a friend of astronomy and a believer in the plurality of inhabited worlds, has left to the Academy the sum of 100,000 francs to be given as a prize to the person who shall first enter into communication of an astre other than the planet Mars."

The will wisely further stipulates that each time the prize has not been awarded for a period of five years, the accumulated interest shall be devoted to a work which will help the progress of astronomy. The intentions of the founder will be scrupulously followed. Astronomers naturally wonder why Mars was debarred.

A Funeral Trolley Car.

Baltimore has a number of fine suburban cemeteries, all of which are reached by some division of the street railway lines, and the company found by putting in a few crossovers they could take a car from any part of the city to any one of the burying grounds. It was, therefore, decided to offer cars for the transportation of funeral parties, says The Street Railway Review. The company built a special car well adapted for the purpose. The car is divided into two compartments, the smaller of which has running its full length another compartment or vault in which the casket is carried. A heavy plate glass door hinged to swing downward gives access to the vault from the outside. When a casket is to be placed in the car, the shelf is drawn out, the casket lifted upon it, and the shelf is then pushed back in place. The larger compartment has twelve cross seats in the center aisle, giving a seating capacity of twenty-four; the smaller compartment has four seats. Heavy black curtains divide this section into two private compartments for the immediate family of the deceased. Floral contributions are piled upon the top of the vault, and can be seen from the street. The car is finished inside and out with black enamel with nickel plated fixtures. The car has been named "Dolores," meaning sorrow, and it is rented at from \$20 to \$25 for each interment.

Automobile News.

The New York Zoological Society will soon operate automobiles of its own for the convenience of the public.

Consul Gibbs reports from Tamatave, December 3, 1900, that Mr. E. Cayeux, a sawmill owner of that city, invites correspondence in regard to liquid-air motors. Correspondence may be conducted in the English language.

A beginning has been made in Chicago to supplant the clanging gongs of public vehicles by more mellow chimes, says The Electrical World. A downtown firm which operates several automobiles was the first to make the change. The Municipal Art Association and the Anti-Noise League are interested in the matter, and it has been suggested that a crusade against gongs be inaugurated.

One of the disadvantages of motor-driven ambulances has been that they do not get the right of way as easily as horse driven vehicles. The familiar clanging of the ambulance gong and the sound of the clattering hoofs of the horses was always sure to clear the way promptly for an ambulance. Now the ambulances have been provided with electric bells which do not differ materially from those which other electric vehicles carry, and the result is that trucks or wagons do not get out of the way as quickly. It has been suggested that compressed air whistles or larger gongs might be used. A return to the old foot gong would probably obviate the difficulty to a certain extent.

An automobile exposition is to be held in Vienna this year, under the auspices of the Automobile Club of Austria and the patronage of the Archduke Francis-Salvator, who is himself a great lover of the sport. The exposition will be held from the 25th of May to the 6th of June, in the Prater, where a large space has been set apart for it. All kinds of automobile vehicles will be represented, including private carriages, towing machines, delivery wagons, motorcycles, etc., besides the accessories and detached pieces, representing the advanced stage of development which the industry has reached in Austria. Foreign exhibitors will also be well represented, and the Automobile Club has extended a cordial invitation to all manufacturers. The club is taking measures to have the foreign products passed through the custom house free of duty on condition that they will be brought back directly after the exposition. It is expected that the German industry will show the advances it has recently made by a large number of exhibits.

Lieut. Edouard Engles, of Frankfort-on-the-Main, has lately made a tour of the Alps with a Benz machine of five horse power, accompanied by his wife and an assistant. The machine weighed 1,500 pounds and carried 175 pounds of baggage. Starting from Frankfort, they passed through Stuttgart and Munich, then Innsbruck by way of Kchelsee and Walchersee, and crossed the Karwendel at an altitude of 3,500 feet, and afterward the Brenner at 4,080 feet. They then continued their voyage by Sterzing, Cortino, Trevisi, to Kenmestri (Venice). The return trip was made by way of Trieste, the passes of Tonal (5,640 feet), Epaica (3,540 feet), then by Tirano and Stilfser Joch (8,260 feet), reaching Bregenz, Friedrichshofen, and Ulm. According to the declaration of the custom house officers at Stilfser Joch, theirs was the first German machine to make the passage at that point. About 1,200 miles in all were made on this trip, and the time was about 99 hours, giving an average speed of about 12 miles an hour, in spite of the high altitudes reached.

Among the novelties is the acetylene automobile which has been recently brought out in France. According to reports, the machine is quite successful in its operation. In one of these machines the truck, which weighs about 1,100 pounds, carries a double motor of four cylinders and two explosion chambers; the motor is of the same general type as the petroleum motor, but has received some modifications to adapt it for use with acetylene. The normal speed of the motor is 2,000 revolutions per minute, and it works without a flywheel; the vehicle is given a mean speed of 12 miles an hour on level road. The motor is not reversible, but there is a mechanism for speed changing which is worked by a foot-pedal; the same device also makes the reversal of the machine at the rate of 2 miles an hour. The usual gasoline reservoir is replaced by an acetylene generator, and the supply of carbide carried on the machine will enable it to cover a distance of about 70 miles at a mean speed of 8 to 10 miles an hour. The motor is designed to develop from 8 to 10 horse power at normal working; it is mounted at the front of the truck, and the explosive mixture acts upon two pistons working in contrary directions, and thus the vibrations are almost neutralized. The apparatus is regulated so that the working of the motor is proportional to the power necessary to develop, and the supply of gas is furnished accordingly. If necessary the motor may be made to work with gasoline. It is expected that further details will be given as to this interesting system.

Archæological News.

Excavations are being carried on at Pompeii around the Basilica.

Many Etruscan tombs have been found in central Italy during the last two years.

The theater at Ephesus has been laid bare by the Austrian excavations. The great harbor appears to be of Greek, not Roman, origin.

L. Lindet considers that the windmill was imported into France and England from the East in the eleventh century, though it may have been in use earlier.

Remains of the ancient theater of Augusta Taurorum (Turin) have been found in the area of the Palazzo Vecchio on the northern side of the ancient town.

Remains of a house of Republican times have been found under the crypt of S. Cecilia in Trastevere, Rome. It was restored in the first part of the second century A. D.

In carrying out the repairs to the Temple of Karnak M. Legrain discovered a city gate. It is the first found in Egypt and is of great height. The chief causes of the fall of part of the temple are the character of the soil and the artificial flooding of the temple.

Drs. Grenfell and Hunt have a great mass of Ptolemaic papyri, some used for inside padding of crocodile coffins, others made up into human coffins, like the Petrie papyri. These latter have not been explored; the former contain at all events the official papers of a komogramateus, or village mayor, of the second century B. C.

The Palazzo Piombino has housed the notable collection of antique marbles transferred to it from the Villa Ludovici. This collection has been acquired by the Italian government and will be placed temporarily in the museum at the Baths of Diocletian. They will be transferred to the Villa Borghese after it is acquired by the government.

Below the pavement of the Æmilian Basilica in the Roman Forum a great antique sewer has been opened. Just where it passes under the steps which led up from the street to the outer arcade of the Basilica the base of a small circular shrine projects into the roadway. It has been suggested that this is the temple of Venus Cloacina, the cleaning goddess.

Cupellation is one of the most ancient of metallurgical processes, and was well known at least as early as the year 600 B. C., says Nature. It was used by the Romans to extract silver from its ores in Spain and at Laurian, but it has been hitherto supposed that the hearths of their furnaces were made of comparatively non-absorbent materials, such as clay and marl, the litharge and other oxides being skimmed off or allowed to flow away in side channels. It is now shown, however, by Mr. Gowland, in a paper read before the Society of Antiquaries in May last, that a silver refinery was worked at Silchester in which argentiferous copper was cupeled on hearths made of bone-ash. Bone-ash has the property of absorbing molten litharge and some other oxides as readily as blotting-paper absorbs water, and apparently only its high cost prevented its use by the Romans in all their later cupellation furnaces. Careful examination of the remains found at Silchester convinced Mr. Gowland that the work there resembled some of the operations formerly practised in Japan, and that it is probable that it consisted in the recovery of the silver from Roman copper coins issued in the third century A. D. The metal contained four per cent of silver, and was cupeled in three furnaces in succession with the aid of repeated additions of small quantities of lead.

American universities have received 118 papyri from the Egyptian Exploration Fund. Among the sixteen papyri for Yale are portions of a lost comedy of the second century and of Plato's Republic of the century before and after Christ. Harvard's share includes a fragment of Paul's Epistle to the Romans, of Aloman, the chief lyric poet of Sparta, 651 B. C., and seventeen other papyri. Columbia receives Xenophon's Hellenica, first century, a letter to the King of Macedonia, and fourteen other pieces. Johns Hopkins gets extracts from Thucydides of the second century, two of Demosthenes on the Crown, and thirteen other fragments. A piece of Herodotus of the second century, a complete contract for a loan in the reign of Nero, and eleven other pieces are assigned to Princeton. Of five papyri for Hamilton College, one is a letter to the Clerk of the Court in the time of Trajan, acknowledging the receipt of a will; and of four papyri to Vassar College, one is about a loan of 3,000 drachmæ of silver, which shows that 8 per cent interest was then paid (third century). Of the total 118 papyri, 29 are presented to the University of Pennsylvania. The larger part of the papyri are from Oxyrhynchus and the rest from various sites. The former is where the "New Sayings of Jesus" were found by the society, and also portions of St. Matthew, Mark, and John, far antedating any other known texts.

Electrical Notes.

The moving sidewalk of the Paris Exposition was a great success; 6,694,308 persons paid for the privilege of using the platforms, while only 2,635,867 used the railway that carried passengers in the other direction.

Recent experiments in wireless telegraphy, in connection with the French fleet, have been so satisfactory that it has been decided to provide the whole Mediterranean squadron with wireless apparatus, which will be subjected to decisive tests during the coming cruise of the squadron.

A new hotel which is to be built on Fifth Avenue will have many interesting electrical features, among which will be a system of electric service elevators, or movable pantries, fitted with electric heating tables. They will be run through every apartment, thereby insuring rapid service and hot food to guests taking their meals in their rooms.

Visitors to Boston have often wondered at the obsolete Back Bay horse car line, which consisted of only two cars operated by four men. All the other street car lines in the city are, of course, operated electrically. The trolley is hardly adapted to that section of the Back Bay district served by the horse car line. The tracks are to be taken up and electric omnibuses are taking the place of the cars.

A test of the Murphy third-rail sectional system took place recently in the Baltimore & Ohio tunnel and in the yards at Baltimore. One of the heavy locomotives ran up and down the yard track at a high rate of speed by the sectional third-rail system. Everything worked perfectly, each switch operated as intended. It took six months to install the system through the yard and tunnel.

Prof. W. Nipher, of Washington University, has discovered that sensitized plates which have been exposed to sunlight and are therefore useless for ordinary photography can be employed in making X-ray photographs. The development of such plates which have been acted upon by the X-rays gives a positive image. Moreover, the plates can be developed by the feeble light of an ordinary lamp, so that the fine details which may be lost by over-development can be carefully observed.

The installation of Marconi's wireless telegraphy upon the vessels plying between Dover and Ostend has proved a great success. In the first test the operators after they had left the latter port, and while still some distance from land, succeeded in communicating with the Marconi station at Dovercourt in Essex, considerably over 100 miles away. The distance from Dover to Ostend is 73 miles, and the operators were successful in transmitting a message from the vessel as she entered the harbor at Dover to the station on the Belgian side. The utility of the system was, however, more adequately exemplified a few days after its installation during a gale. The vessel encountered heavy seas, and her passage was consequently delayed. The operators, however, continued in communication with the shore, and were able to announce their bearings from time to time. Messages were also transmitted for the passengers, while one was received from Brussels. The system has been of great advantage in connection with the navigation of the vessel, since on more than one occasion the captain has received notification by ether communication of the presence of fogs off the Belgian shore, and has, therefore, been able to reduce the speed of his vessel accordingly.

The Central London Electric Railway has met with such popularity that the officials are experiencing considerable difficulty in preventing overcrowding of the carriages. The daily conveyance of passengers now amounts to over 200,000, and on wet days the complement is greatly increased. One solution of the problem is the lengthening of the trains by the addition of one or two extra carriages, but if this is resorted to the platforms will have to be extended. Another suggestion is a more frequent service, but the success of this scheme depends entirely upon the public itself. At the present time the trains are only scheduled to make a 15 seconds stoppage at the stations, but, of course, at some places such a short stoppage is impossible. The duration of a stop must depend upon the number of passengers who desire to detrain at that particular point. The company suggests that the passengers should prepare to leave the train before it reaches their destination. If this were followed no doubt the difficulty would be to a certain extent solved. The trains are at present running at intervals of 3 minutes, but this service is to be increased to 2½ minutes headway. Probably this latter will be the limit at which the trains can run with perfect safety. The earning capacity of the railway is enormous, as may be recognized from the number of passengers carried, but up to the present nothing has been published regarding the expenses, so that it is impossible to estimate what dividend the railway will pay.

DE DIETRICH AUTOMOBILES. AMEDEE BOLLEE (FILS) SYSTEM.


The type of automobile exhibited by the De Dietrich Company is shown in the illustrations and diagrams. The truck rests upon the axles by long and elastic springs; as it carries all the organs of the motor and the transmission, any form of carriage body may be used. Two of the principal types are shown in the engravings, one of these being a racing machine. In front of the truck is placed the motor which is supported by a cross-tube and a T-iron. The starting of the motor is effected by the handle, whose shaft carries at the other end a bevel gear, which engages with a similar gear on the motor shaft. The movement of the motor is transmitted to the rear by the belt, *J*. The speed-changing mechanism, shown in Fig. 2, is placed in the rear of the truck, and includes four speeds and reversal. The two main pulleys, *P P'*, mounted on the intermediate shaft, *A*, carry the belt from the motor; the pulley, *P*, is fixed, while *P'* is loose on the shaft. The fork, *F*, displaces the belt to the fixed pulley and starts the system, the fork being controlled by a handle within reach of the conductor and a series of levers. The shaft, *A*, is mounted in two bearings. The gears, 1, 2, 3, 4, for the different speeds are mounted on a collar which turns with the shaft, but is keyed to it and may be displaced to one side or the other, throwing the different gears into connection with the gears, 1', 2', 3', 4', on the shaft of the differential. The gears are displaced by a lever, *L*, which engages in a collar, *r*. In the figure showing the speed-changing device the wheels,

4 and 4', are engaged, this giving the maximum speed; by pushing the lever the wheels, 3, 3', are engaged and so on to 1 1' which gives the slowest speed. The rear movement is obtained by the small pinion, *p*, mounted on a shaft carried at the end of a lever, *V*; the pinions, 1 1', are placed near together, but without touching, and the lever then moves the small

steam from the cooling chamber of the motor passes into a condenser formed of tubes, placed generally in front of the vehicle; the steam is condensed in whole or part and the water returns to the cylinder jackets by a tube passing below the motor. For a motor of 9 horse power, 12 or 14 yards of cooling tube placed in front of the vehicle allow a whole day's run without renewing the water. The motor is provided with a centrifugal governor which acts upon the exhaust valves. The carbureter is shown in Fig. 4. The reservoir, *R*, carries the cylindrical float, *F*; the gasoline arrives by the tube *r*, and a constant level is obtained in the reservoir by the conical plug, *c*, which stops the orifice at a certain level. The tube, *T*, below, communicates with the second part, containing two cylindrical chambers. The lower chamber admits air by the opening, *A*, and in the upper is the aspiration orifice, *D*, of the cylinders. In the center is a circular plate, pierced with holes carried upon the rod, *V*, whose lower part enters into the conical orifice, *t*, of the gasoline tube. Owing to the aspirating effect of the piston, the gasoline comes out in jets and strikes the plate, producing an atomizing effect, and the air arriving by the orifice, *A*, is thus carbureted, and passes into the upper cylinder and thence to the motor. The gasoline supply is regulated by a screw above, which limits the course

of the vertical rod; the screw is operated by a lever within reach of the conductor. The steering of the vehicle is effected by a hand-wheel whose movement is transmitted to the front wheels by a system of levers. The conductor has also at hand the brake lever, the speed-changing device for the pinions, the lever for regulating the carburetion, and a lever which acts upon the governor spring and thus changes the speed of the motor. A second brake is provided, which acts upon a collar on the main driving gears.

RAFIA fiber is a staple article of commerce in Madagascar. The Hovas use the under part of the leaf, split very fine, as a warp with a weft of white silk producing an article called silkamba, which is sold both in Europe and America. The coast tribes use it for clothing, but of coarse quality, with dyed stripes of indigo, saffron, black, and a dirty green. It is a cold, comfortless-looking material and does not lend itself to graceful folds, and when two natives come down a road clad in new rafia shirts the noise produced is somewhat similar to that of two wire meat covers rubbing together.



DE DIETRICH RACING MACHINE.




Fig. 3.—THE DE DIETRICH MOTOR.




Fig. 2.—THE SPEED-CHANGING GEAR.




Fig. 4.—THE DE DIETRICH CARBURETER.





Fig. 1.—SIDE ELEVATION OF THE CARRIAGE FRAME.



DE DIETRICH MOTOR CARRIAGE.



DE DIETRICH MOTOR CARRIAGE WITH TOP UP.

RUNNING DOWN WHALES.

BY CHARLES FREDERICK HOLDER.

The coast of Southern California is protected, to a certain extent, by the islands off shore. The group begins at Santa Barbara with San Miguel; then come Santa Rosa, Santa Cruz, Anacapa, and farther out to sea, thirty miles, San Nicolas. The next following south are Santa Barbara, Santa Catalina, San Clement, and then with a break of seventy miles the Coronadoes. These islands are almost parallel to the coast range and constitute virtually an out-to-sea coast range of mountains which, in all probability, were thrust up at the time the coast was formed, leaving a deep depression between them and the mainland.

This region of extremely deep water is a famous roadway for whales, several kinds being found here feeding upon the vast schools of jelly fishes which are nearly always present. The whale most common is the California gray, which goes every year to the shallows of the Gulf of California to give birth to its young, then moving north along the California coast in what is virtually a great procession. At this time the channel is the sporting ground for the huge animals, and nearly every steamer that crosses sights a school, the scene forming one of the attractions of the trip, as the whales, far from being wild or timid, sometimes evince a playful mood, or, incited by curiosity, come near the steamer, affording the passengers a near view of the largest of living animals.

This sociable disposition has resulted in several encounters between the whales and vessels in which the former have always come off second best. Some years ago a steamer on the trip from San Pedro to San Francisco struck some body, supposed at first to be a log. Several of the men were thrown to the deck; the wheel turned over so violently that the helmsman was also thrown down, and the steamer for the moment came to a standstill. All hands were called, the pumps sounded, and as the mate ran aft he saw a large whale lashing the water astern. The vessel had struck it directly back of the right paddle and evidently crushed it down, rising over it. This whale drifted into Santa Catalina some days later and was towed into one of the little bays of the coast where it was cut up by the fishermen.

During the summer of 1900 the steamer "Hermosa" killed a whale off San Pedro, which was at least eighty feet in length. The steamer was plowing along at a rate of twelve miles an hour when suddenly a large whale rose to spout directly in front of her, placing itself inadvertently across her bows, so that the blow was struck fairly. The shock created a sensation on board and the blow was so violent that several people were thrown from their feet. It was supposed that the vessel had struck a sunken rock; she stopped for a few seconds, trembled, then rose about three feet, heeling slightly, then resumed her course, passing through a mass of blood which colored the water, showing that she had plunged into some large animal. A dead whale was sighted two days later and for several days, on account of its size, it drifted up and down the coast with the tide, defying the efforts of speculative fishermen to secure it. Finally a heavy sea tossed it on the coast at the resort of Redondo, where it was hauled in at high tide, and when the latter went out

left a marvelous spectacle of the remains of one of the largest of living animals. Hundreds of people visited the spot before it was dismembered. A long wound told the story of its contact with the steamer that was wholly uninjured.

Doubtless if the records of shipping disasters were examined many instances would be found where vessels had crashed into whales with results fatal to the animal and more or less injurious to the vessel. In this connection a curious incident may be related regarding the actions of a school of whales at the island of Santa Rosa, Cal. The channel between this island is narrow and often extremely rough, and during a storm it was believed by those on the island that the whales became demoralized, as they deliberately



CALIFORNIA GRAY WHALE KILLED BY A STEAMER.

ran ashore, and the remarkable sight of five or six large whales was observed helpless on the sands. Their bones remained for a long time on what became known as the whales' graveyard.

A GLIMPSE OF THE NAVAL BATTLE OF SANTIAGO.

To those of our readers who take a lively interest in the history of the United States navy, the engraving which we present of one of the most important phases of the battle of Santiago will possess special attraction. In proportion to its size there is no navy, surely, to whose credit stands such a long list of successful encounters, and in the absolute completeness of the victory gained, even after every allowance has been made for the numbers and power of our ships and the superior discipline of the crews, this battle off the south coast of Cuba will always stand pre-eminent.

Santiago was a triumph both of material and men; a victory the winning of which commenced long before the war-cloud arose and the first gun was heard. The swift destruction of the flower of the enemy's fleet was merely the culmination of a work for whose in-

ception we must go back to the time when our ships first took form on the designer's draughting board, and our ordnance experts drew the diagrams of gun and gun mount, or the engineers converted their allotted share of the displacement into engines, boilers and fuel.


Our engraving of the famous battle was made from one of a series of historical paintings which the retiring Chief Naval Constructor, Rear-Admiral Hichborn, has had painted to represent the development of naval architecture in America. These paintings, which are hung in the office of the Chief of the Bureau, commence with the caravels of Columbus, 1492, and end with the "Pennsylvania" class of battleships of 1901. In addition to this series, and as a climax to the story of naval progress, a large painting of the battle of Santiago de Cuba, the latest engagement which reflected credit alike on the design, the material, and the men of the United States navy, has been added. As almost all the vessels engaged in this action were from designs of which the retiring Chief Constructor has had supervision, there was something peculiarly fitting in placing a painting of this engagement among those of the vessels that engaged in it.

It will be remembered that between 9:35 and 10 o'clock on the morning of Sunday, July 3, 1898, when the Spanish vessels attempted to escape from Santiago de Cuba, the United States' blockading fleet consisted of the "Brooklyn," "Texas," "Oregon," "Iowa," "Indiana" and the auxiliaries "Gloucester" and "Vixen," arranged in a semicircle about the harbor entrance, about 2½ to 4 miles from shore, that being the limit of the day blockading distance. Two other vessels of the fleet, the "Massachusetts" and the "New York," were unavoidably absent, the former having left at 4 o'clock A. M. for Guantanamo to coal, and the latter to convey Rear Admiral Sampson to Siboney for a conference with General Shafter.

When the Spanish fleet cleared the harbor's entrance, it became at once apparent that a running fight was planned instead of an attack upon the American fleet. This method of escape attempted by the Spanish fleet, all steering in the same direction and in single formation, made the scheme of battle very easy for the American squadron.

The first rush of the Spaniards to the westward carried them past a number of the vessels of the blockading squadron, whose crews were at Sunday "Quarters for inspection," but when the warning, "Enemy's ships escaping," was reported from the lookout and "General quarters" sounded, the men dropped clean clothes and polished accouterments and with a cheer sprang to man the guns. The thorough training they had received in the service quickly demonstrated to the enemy that they had encountered no ordinary opponent, for in less than three-quarters of an hour from the time the last Spanish vessel had left the harbor, four of the six vessels comprising the fleet had been set on fire and beached.

The time selected for the painting was about 10:20 o'clock A. M. at a point off Cabrera Point looking eastward. The Spanish ships are seen close in shore, the "Viscaya" leading and the "Colon" following, the "Maria Teresa" and "Oquendo" on fire turning to run




THE NAVAL BATTLE OF SANTIAGO, AS SEEN OFF CABRERA POINT.

in shore, and the torpedo boats "Furor" and "Pluton" practically destroyed. The American fleet is shown in the foreground with the "Brooklyn" in the lead, followed by the "Oregon" and "Texas," while in the distance are seen the "Iowa," "Indiana" and the auxiliary yacht "Gloucester." The engagement at this time and in this position was probably the most exciting and picturesque of any during the battle, and its portrayal by the artist is very realistic and inspiring.

THREE RECENTLY PATENTED NOVELTIES.

In certain forms of fire-hydrants, the face of the valve is moved across the seat, whereby not only the valve, but also the seat, is injured. To overcome this objection Robert Hughes, of Waterford, N. Y., employs a novel arrangement of levers by means of which the valve is made to move parallel to a desired plane.




A SIMPLE VALVE MECHANISM FOR FIRE-HYDRANTS.

The valve is provided with two blocks, one fixed and the other capable of sliding in a slot. To each block one end of a lever is pivoted, the other end of one lever being pivoted to a support loosely receiving the end of a screw stem, and the other end of the second lever being pivoted to a nut threaded on the stem. The levers are pivoted together. When the screw-stem is turned in one direction the nut is carried up and the valve drawn from its seat. The sliding block as it works in its seat reduces the downward travel of the valve to a minimum. When the levers are pivoted together at their middle points there is no downward travel of the valve.

A self-marking try-square is an invention patented by Isaac W. Stephens, of Sardis, Tenn., which is distinctly novel in form and operation. The handle of the try-square is hollowed to receive a spring-actuated push-pin joined by a pin and slot connection with one end of a lever fulcrumed near its middle. The other end of the lever is loosely received by a recess in a scoring-plate having reciprocating movement in the channeled blade of the try-square. The edge of the scoring-plate is provided with elastic spring tongues formed with prongs bent in opposite directions. By pressing upon the push-pin the scoring-plate is moved in one direction. When the push-pin is released the spring moves the scoring-plate in the other direction.

A very simple and ingenious pendulum adjuster has




THE DIVIDED PALLET-ROD FOR ADJUSTING THE BEAT OF A PENDULUM.

been devised by Simon B. Parker, of Springfield, Mass. The novel feature of the invention consists in employing a divided pallet-rod, the two sections of which are connected by means of separable metal disks held together by a clamping-screw. Proper friction can be given to the disks by the adjustment of the clamping screw. By simply starting the pendulum to bank the pallet on the escape-wheel, the pendulum swings within its normal arc by reason of the adjustment of the disks. The arrangement can easily be applied to old clocks by cutting the pallet-rod in two and securing the disks in place.

REPAIRING A BROKEN SHAFT AT SEA.

On the 12th of December last, at three o'clock in the afternoon, the Danish steamer "Louisiana" was in the Gulf of Mexico, about sixty miles from the mouth of the Mississippi River, loaded with a full cargo for Aarhus, Denmark, when suddenly the first intermediate shaft broke completely through and the engines commenced to race violently. On stopping the engines it was found that the accident had happened within the shaft tunnel, a diagonal fracture 28 inches in length having occurred in the first intermediate shaft. The gland-bush in the watertight partition, and the foremost bearing, were found to have been demolished, as well as the head of the second bearing. On examining the shaft, which measured 11 1/4 inches in diameter, it was found that only one-quarter of its length was intact.

Repairs were started at four o'clock, one hour after the accident, the first work to be done consisting in boring two 1 1/2-inch holes through the fracture, one near each end, the engine-room force being also set to work at the same time forging the special tools required for the repairs. To hold the broken ends together two band-rings were taken from the hoisting gear and clamped around the shaft, and in order to get rid of the vibration from the propeller the tail-end shaft was disconnected. It took 39 hours altogether to complete the boring of the two 1 1/2-inch holes. During the boring a band was taken from the foremast of the steamer and forged into a collar 1 1/2 inches thick by 6 inches in width, and of the diameter of the shaft. As soon as the holes had been bored to 1 1/2 inches, work was started on enlarging them to a diameter of 2 1/4 inches, and two bolts were taken from the main bearing, cut down to length and bolted through the shafts, as shown in the drawing. The forged collar was then fitted on and Babbitt-metal was poured into the joint. The first bearing box was replaced by a wooden one, and the tail-end shaft and the repaired intermediate shaft were then connected up. The repairs were completed at one P. M. on the 17th, the chief engineer and his assistants having worked continuously day and night for nearly five days. At three



THE SHAFT REPAIRED.

P. M. the vessel started at slow speed and reached the lightship at the South Pass of the Mississippi six hours later, where she anchored until she was picked up by a tugboat and taken into the river. The greatest credit is due to Capt. Jensen and the engineer staff for the pluck and resourcefulness shown in the carrying out of such a repair job at sea.

The Charleston Exposition.

The new Exposition at Charleston will open December, 1901, and will remain open until June, 1902. It is intended to advertise to the world the progress of South Carolina and the neighboring Southern cities, and the advantage Charleston enjoys as a natural seaport for the trade between the West Indies and the United States. There will be a large number of exhibits from the West Indies, and from Florida, and the whole exposition will be characteristic of the tropics. The grounds cover about 250 acres of land, and are situated on the Ashley River, 4 1/2 miles above Charleston. As the river is navigable for large ships up to that point two or more naval vessels will be stationed there. An artificial lake will be constructed near the middle of the grounds extending over an area of 30 acres. In the middle of the lake will be an electrical island. Two old colonial houses situated on the exposition grounds will be retained. The plaza will be 1,200 by 900, and there will be an auditorium capable of holding 6,000 persons. On it will also be situated the Cotton Palace and the buildings of Commerce and Agriculture. The style of architecture will be Spanish-Renaissance. The materials used will be pine and staff.


Harvesting Extraordinary.

The bulk of the flax grown in Kittson County, Minn., was harvested under very remarkable conditions. The fall was unusually wet, and it was found impossible to get on the fields. Freezing weather came almost immediately thereafter, and an extremely heavy fall of snow. The old methods had to be abandoned, and mowers brought into use. The sickle bar was entirely under the snow, and after the flax was cut it still stood as erect as ever, but the hay-rake following had no trouble in gathering it, as it was so thick and so entwined that the rake caught it all.

A SIMPLE AND EFFICIENT CLIPPER GRINDER AND SURFACE GRINDER.

The subject of the accompanying illustration is a novel grinding device for sharpening the blades of clippers. The inventor of the machine is William Taber, and its manufacturer J. Van Benschoten, 14 to 20 Catherine Street, Poughkeepsie, N. Y.

As our illustration shows, the machine comprises essentially a frame having a horizontal arm and a base. Between the horizontal arm and the base a vertical shaft, carrying a 14-inch emery wheel, turns on a cone bearing. Power is transmitted by belt and pulley. In its upper face the stone is provided with a circular depression four inches in diameter.




THE VAN BENSCHOTEN CLIPPER GRINDER.

On the five inches of flat grinding surface thus furnished clippers are held parallel and moved laterally over the two edges, whereby the surface of the stone is maintained both flat and true. In order that the stone can be trued without removing the vertical shaft from its bearing, a special truing attachment has been devised consisting of two half-inch rods, fitted in proper supports on which a star-wheel emery-dresser is moved gradually across the surface by means of a small crank and a screw. The dresser is also adjustable, so that any cut desired can be made. Thus not only can the stone be trued absolutely, but all glaze is removed as well.

Owing to the accuracy with which the surface of the stone can be ground, this device can be used on any light surface, such as the blades of sausage cutters, meat choppers, dies, cutter knives, and the like.

The Current Supplement.

The current SUPPLEMENT, No. 1312, has many interesting articles. "The Ancient History of Water Engineering" is by James Mansergh. "Observations on Crookes Tubes" is by H. Westbury. "The Optics of Tri-Chromatic Photography" is by F. E. Ives. "Mammals and Reptiles; or, What Was the Ice Age?" by



TRY-SQUARE WITH SELF-ADJUSTING SCORING DEVICE.

Joshua Rutland, is a most interesting paper. "The Mosquito as Transmitter of Micro Organisms" is by Dr. R. Menger. "The Galileo Museum at Florence" is the subject of an interesting engraving. The usual Consular matter and Trade Notes and Receipts are given.

Contents.

(Illustrated articles are marked with an asterisk.)

Automobile, De Dietrich*.....	120	Planets, communication with....	118
Books, new.....	123	Rhone, hydraulic power of.....	118
Build, are you about to?.....	115	Science notes.....	115
Buoys, petroleum illuminated*.....	117	Shaft, repairing broken*.....	122
Dredge, dipper*.....	116	Silk manufacture*.....	113, 118
Exposition, Charleston.....	122	Smokeless powder and gun erosion.....	114
Gramme, Z. T.....	115	Steamers, high-speed.....	114
Grinder*.....	122	Sugar manufacture, Russian.....	116
Harvesting, extraordinary.....	122	Telegraphy, wireless, Tesla's.....	114
Inventions, prizes for.....	114	Trolley car, funeral.....	118
Light, therapeutic action of.....	117	Try-square.....	122
Naval battle, Santiago*.....	121	Tunnel, Rapid Transit.....	114
Novelties recently patented*.....	122	Whales, running down*.....	121
Orchestra-man*.....	117	Yacht, royal.....	114
Our business and personal want column.....	115	Zodiacal light.....	115

RECENTLY PATENTED INVENTIONS.

Engineering Improvements.

FEEDING SCALE-PREVENTIVES INTO BOILERS.—GEORGE NEUBAUER, Manhattan, New York city. The apparatus comprises an injector connected at the inlet with the discharge of a boiler feed-pump and at the outlet with the suction of the boiler feed-pump; and a container for the scale-preventive, discharging into the injector. By means of this apparatus the engineer can force more or less of the preventive into the boiler, according to the condition of the feed-water.

Mechanical Devices.

CAR-BRAKE.—JOHN H. DIERCKS, Minneapolis, Minn. One end of a brake-band on one of the wheel-hubs is connected with a lever, and the other end of the band is connected with a second lever. A rock-shaft has operative connection with the first lever; and a brake-rod has connection with the rock-shaft. Band-brakes, co-acting with the other wheels, have operative connection with the lever and the rock-shaft. The brake is set upon one wheel by manual exertion, and this brake thus set operates all the others. Upon releasing the brake-rod the several brake-bands will be relieved of pressure.

CLEARING DEVICE FOR LIFE-BOATS.—ERICK WOLFGANG, London, England. This chock-releasing device for life-boats comprises an overhead support for the life-boat, normally inactive, and a keel-support, normally supporting the boat. This keel-support is movable under the control of the operator, to shift the keel-support from under the life-boat and allow the latter to hang from the overhead support. The keel-support comprises a number of center keel-blocks and side keel-blocks movable independently. One side block and the bottom keel-block are arranged to move vertically, and the other side keel-block is hinged to swing transversely relatively to the life-boat. A single operator can release the boat in case of an emergency.

FIRE-ESCAPE.—FRANCIS J. HUGH, Manhattan, New York city. Mr. Hugh has already received a patent for a fire-escape in which a cable unwinds from a pulley controlled by a speed-checking governor. The present invention is an improvement upon this device, and relates primarily to a governor. The principal object of the invention is to utilize a wire rope or cable in such a manner that a positive rotation of the pulley over which the wire passes, and a consequent actuating of the governor co-acting with that pulley, takes place. The ordinary ropes frequently used in fire-escapes are objectionable, owing to the danger of being burnt. In order that the cable may not slip, initial friction devices and a V-shaped groove in the pulley are provided. The heavier the load on the cable, the less danger will there be of a cable's slipping, so that the governor is caused to operate properly and check the speed of the load.

Miscellaneous Inventions.

RADIATOR.—JOHN F. THOMPSON, Manhattan, New York city. The principal object of this invention is to provide a radiator with an auxiliary water-heating device which may be used when comparatively little heat is required and when the radiator is cut off from the main steam or heating boiler. The auxiliary heat supply is automatically controlled.

PAPER BOX.—JOSEPH T. CRAW, Jersey City, N. J. In order to seal the ends of sugar-boxes siftlessly, Mr. Craw provides his box with a snugly fitting interior sealing-strip having adhesive material upon its outer face and a sealing-flap portion of a size to fold over the outside of the sealing-strip and to cover the strip entirely so that its outer surface will be entirely invisible. Thus the flat portion of the box is cemented to the outer face of the strip; the ends of the strip are cemented to the body of the box, and the adhesive material is forced into the spaces between the edges of the flap portion and the sides of the box. Thus the flap portion is held in a folded position, and, together with the strip, closes the box to prevent sifting.

HOP-DRYING BOX.—ADOLF WOLF, Silverton, Ore. The inventor has provided a construction by which a hop-drying box can be readily turned upside down without discharging the contents, the top being left open for a thorough evaporation and escape of steam. The box has a removable top and a removable bottom, constructed and secured in a novel manner to attain the desired end.

FISH-TRAP.—DANIEL H. WELCH and JOB H. LAMLEY, Astoria, Ore. The object of the invention is to facilitate the capture of fish by traps. To this end the inventors employ a movable lead with novel devices for securing one end thereof. Between this movable lead and the stationary or main lead of the trap the fish are impounded, so that they are forced along the main or stationary lead into the pot or crib of the trap.

DEVICE FOR DISINFECTING TRANSMITTERS AND RECEIVERS OF TELEPHONES.—CYRUS F. AXTELL, Manhattan, New York city. The necessity for the application of some efficient and simple means of disinfecting the receivers and transmitters of telephones has long been recognized. The present invention provides means for accomplishing this much-desired end. The disinfecting agent employed by the inventor is ozone or ozonized air, the

antiseptic properties of which are well known. The ozone necessary for the purpose is produced through the agency of a current of electricity generated by the "magneto" forming a part of all ordinary telephones, although the necessary current may be obtained from other sources.

BALE-TIE.—EDWARD T. WAIN, Sterling, Ill. A wire has its ends formed with loops, one of which is bent forward and upward, and the other of which is bent forward and downward. The short ends of the loops are normally in contact with the main portion of the wire, but adapted to spring away therefrom. The construction is so simple and durable that the tie can be easily and cheaply manufactured. The ends of the tie safely interlock to hold the baled material in place.

TOP FOR POWDER, COLOGNE OR SAUCE BOTTLES.—JACOB A. MÖLLER, JR., Brooklyn, New York city. In its upper portion this top has an opening in line with which is a washer. Below this upper washer is a lower washer having a registering opening. Through the opening in the top and between the two washers a slide has endwise movement. The slide has an opening adapted to register with the openings in the washers and in the top. The washers, between which the slide has movement, tend to clean the slide from any substance that may adhere. By removing the top, the various parts may be conveniently cleaned. By means of the top, the discharge of the material contained in the bottle can be readily regulated.

SORTING DEVICE.—JACOB PFEIFFER, Kaiserslautern, Bavaria, Germany. The invention provides a machine for separating flour from dust and from semolina. A series of superposed rotary disks or spreaders of a diameter increasing downwardly from disk to disk are employed, so that the material is subjected to a centrifugal action of progressively-increasing strength. A disk below the topmost disk is apertured centrally. Each of the disks flares downwardly to throw the material scattered by the spreaders upon the next spreader below. A ventilator forces an upward current of air through the apertured disk or disks and between the peripheries of the disks and their surrounding rings. An upwardly-flaring, annular deflector extends from the upper contracted edge of the uppermost ring.

BOLT AND NUT LOCK.—WILLIAM H. PARDEE, Antigo, and JAMES H. MORGAN, Rhineclander, Wis. The bolt has a reduced portion and an elongated head. The nut has an inner thread. A threaded sleeve screws in the nut and has an elongated bore for the passage of the head, a reduced portion, and also an elongated recess at the outer end at an angle to the bore for engagement by the head, so that the sleeve is held from turning in the nut when the latter is turned.

PRACTICE-BALL.—FRANCIS OAKLEY, Newport, R. I. The inventor has devised a ball to be used by baseball players in practicing. Externally the ball is similar to the ordinary baseball. The ball, however, is provided with an elastic cord which may be attached to the wrist of the player, so that the ball, when thrown, will be returned to the hand.

ANVIL.—NELSON H. SNYDER, Newton, N. J. This anvil is especially adapted for horseshoers or blacksmiths, and is so made that all horseshoe work can be done without requiring the constant movement of the smith to and from the ends of the anvil. Extended bearing surfaces are provided flush with the upper face of the body of the anvil, which extended bearing surfaces are especially useful when working upon axles and when forming the toe and side clips of horseshoes.

TARGET.—WILLIAM G. SMITH, Glendale, Queens, New York city. Mr. Smith has invented a target representing pigeons in flight, which target can, therefore, be used to take the place of the live pigeons usually employed by sportsmen in trials of marksmanship. In order to give the trial the appearance of real bird-shooting, the target carries a cartridge which, when discharged, causes feathers to fly. The bird not only drops as in death, but the feathers fall as the bird falls.

WOVEN PILE FABRIC.—HOVCEP SARAFIAN, Titusville, Pa. The invention provides a pile fabric which has a fine appearance and excellent wearing qualities, and which can be readily woven without requiring highly skilled labor. Warp-threads and pile weft-threads comprise the fabric. Each of the weft-threads consists of a strip formed of fringe-threads, at the center of the length of which, binding-threads are interwoven. The strip is folded and the parts are secured together to form a strip with a woven back, from which all the fringe-threads extend in one direction.

SUSPENDING ATTACHMENT FOR MANTLES.—WARREN D. HANN, 132 Arch Street, Philadelphia, Pa. The means of suspending incandescent mantles of Welsbach lights have not prevented injury and destruction during transportation. To remedy the evil, a suspending attachment is described in this patent, which consists of an asbestos device made of such length and so attached to the ordinary rigid loop of the mantle and to the hook of the ordinary rigid wire or rod support as to be free to swing laterally in all directions and to allow corresponding movement of the top portion of the mantle.

TESTER FOR BLAST-CAVITIES.—WILLIAM GIBBONEY, JR., Bane, Va. Mr. Gibboney has invented a tester for ascertaining the size of the preliminary blast-cavity usually em-

ployed in blasting rocks for railroad and other construction, so that if not large enough it may be enlarged by additional cartridges of dynamite, or if already larger than desired, it may be sufficiently filled with powder to produce the proper lifting and dislodging effect on the rock without waste of powder. Thus the difficulties of enlarging the lower end of a drilled hole—"springing the hole," as it is usually called—are overcome.

CONVERTIBLE TUB.—MRS. N. F. HURDEL, Manhattan, New York city. The tub is so constructed that it can be used either as a bath-tub or as a laundry-tub. When the bath-tub is to be used as a laundry-tub, a partition is inserted which divides the tub into two compartments. By means of a pivoted spigot hot or cold water can be directed into either compartment. In order that the tub can be raised from the low position of a bath-tub to the raised position of a laundry-tub, or *vice versa*, a simple form of gearing is provided which can be easily operated by a small handwheel.

Designs.

BELT.—LOUIS SANDERS, Brooklyn, New York city. The upper central marginal portion of the belt is a concaved line, gradually merging into convex lines extending to the edges of the belt. The ends of the belt incline from the top downward and outward, and the width of the belt at the ends is greater than at any other portion.

BOX FOR HYPODERMIC NEEDLES.—FAIRLEIGH S. DICKINSON, Bayonne, N. J. The design provides a tray body and a large bridge within the tray body. In the bridge are a series of elongated openings for the reception of the needles.

SKIRT-SUPPORTER.—WILHELMINA MCW. LOWRIE, Buffalo, N. Y. The design shows a very simple and efficient skirt-supporter, comprising a triple-hooked head from which an apertured shank springs.

NOTE.—Copies of any of these patents will be furnished by Munn & Co. for ten cents each. Please state the name of the patentee, title of the invention, and date of this paper.

NEW BOOKS, ETC.

THE PROCESS YEAR-BOOK FOR 1900. Edited by William Gamble. London: Penrose & Company. New York: Tennant & Ward. 1900. 8vo. Pp. 111. \$1.50.

Penrose's pictorial annual, of which the present is the sixth volume, is illustrated as usual with a most elaborate series of engravings and plates which show the wonderful possibilities of the half-tone, especially the three-color process. Some of the latter are not very successful. The literary contents are thoroughly up to the usual high standard. The interior views of some of the large German process establishments are very interesting.

TECHNOLOGISCHES LEXIKON. Handbuch fuer alle Industrien und Gewerbe. Uebersicht der gesamten Technologie der Jetztzeit, zum Gebrauche fuer Techniker, Chemiker, Gewerbetreibende, Kaufleute u. s. w. Unter Mitwirkung von Fachgenossen redigirt von Louis Edgar Andes. Illustrated. Parts 11 to 15. Vienna: A. Hartleben. 1900. Post octavo. Price per part 20 cents.

TASCHENBUCH DER DEUTSCHEN UND DER FREMDEN KRIEGSFLOTTEN, 1901. Herausgegeben von B. Weyer, Kapitänleutnant a. D. München: Verlag von J. F. Lehman. 1901. Illustrated. 12mo. Pp. 273. Price 75 cents.

Capt. Weyer has compiled a handbook which presents in the most concise form conceivable everything that is worth knowing about the sea power of the countries of the world. A careful examination of the book convinces us that its information is as trustworthy as that conveyed by any of the more pretentious naval annuals, with the additional merit of being much briefer. The paragraph on page 92, in which the possibilities of a war with the United States—for that, we take it, is the country referred to by the writer—growing out of commercial jealousy, is too preposterous to warrant insertion. Moreover, the argument might as readily be used by an American against Germany.

HANDBUCH DER INGENIEURWISSENSCHAFTEN. Dritter Band. Dritte vermehrte Auflage. Herausgegeben von L. Franzus, A. Frühling, H. Garbe, J. Schlichting, und Ed. Sonne. Dritte Abteilung. Erste Lieferung. Leipzig: Wilhelm Engelmann. 1900. Large octavo. Pp. 352. Price, paper, \$5.

The third part of the third volume of this admirable handbook is devoted to exhaustive dissertations on the ocean and navigation; the effect of the sea on coasts; shore structures; the effect of the sea on estuaries, and seaharbors. The text is illustrated by many clear engravings. In the back of the book will be found fourteen handsome plates.

DER HAUSFREUND. Illustrierter Familien-Kalender fuer das Jahr 1901. Buffalo: Published by the Volksfreund.

SURVIVALS. A Book of Poems. By Lewis V. F. Randolph. Embellished by Bryson Burroughs. New York and London: G. P. Putnam's Sons. 1900.

Business and Personal Wants.

READ THIS COLUMN CAREFULLY.—You will find inquiries for certain classes of articles numbered in consecutive order. If you manufacture these goods write us at once and we will send your name and address to the party desiring the information. In every case it is necessary to give the number of the inquiry.

MUNN & CO.

Marine Iron Works. Chicago. Catalogue free.

Inquiry No. 26.—Wanted the name and address of a manufacturer of a continuous feed machine that will press most of the moisture out of a substance containing about 90 per cent. The amount of wet matter to be pressed is about 1,000 tons daily.

For hoisting engines. J. S. Mundy, Newark, N. J.

Inquiry No. 27.—Wanted the name and address of a manufacturer of retorts, machinery and tools for the manufacture of wood alcohol and its by-products, such as gray acetate of lime, etc.

"U. S." Metal Polish. Indianapolis. Samples free.

Inquiry No. 28.—Wanted the name and address of a manufacturer willing to undertake the manufacture of a small metal household utensil consisting of three parts, viz., steel blade, a cast metal handle and a thumb-screw, all nicked, to be made in quantities.

WATER WHEELS. Alcott & Co., Mt. Holly, N. J.

Inquiry No. 29.—Wanted the name and address of a manufacturer of small porcelain-lined water tanks for refrigerators.

Yankee Notions. Waterbury Button Co., Waterbury, Ct.

Inquiry No. 30.—Wanted the name and address of a manufacturer of a die or stamp such as is used in cutting out men's gloves.

Handle & Spoke Mch. Ober Mfg. Co., 10 Bell St., Chagrin Falls, O.

Inquiry No. 31.—Wanted the name and address of a manufacturer of steel pressed collars for horses.

Rigs that Run. Hydrocarbon System. Write St. Louis Motor Carriage Co., St. Louis, Mo.

Inquiry No. 32.—Wanted the name and address of a place where a manufacturer may examine, and if so desired, purchase patents and novelties which can be made in completely equipped brass, woodworking and leatherworking shops.

Special and Automatic Machines built to drawings on contract. The Garvin Machine Co., 141 Varick St., N. Y.

Inquiry No. 33.—Wanted the name and address of a manufacturer of paper box and paper bag machinery.

Design and Construction of Oil Engines, new book by Goldingham, by mail \$2. Spon & Chamberlain, 12 Cortlandt St., New York, U. S. A.

Inquiry No. 34.—Wanted the name and address of a manufacturer of ice harvesting machinery.

Hand Book of Corliss Engines: 224 pages, 68 illustrations, cloth binding. By mail \$1.00. Catalogue free. Amer. Ind. Pub. Co., Bridgeport, Ct.

Inquiry No. 35.—Wanted the name and address of a manufacturer of water stills without worms.

The celebrated "Hornsby-Akroyd" Patent Safety Oil Engine is built by the De La Vergne Refrigerating Machine Company. Foot of East 138th Street, New York.

Inquiry No. 36.—Wanted the name and address of a manufacturer of a portable, centrifugal gold separator.

The best book for electricians and beginners in electricity is "Experimental Science," by Geo. M. Hopkins. By mail, \$4. Munn & Co., publishers, 361 Broadway, N. Y.

Inquiry No. 37.—Wanted the name and address of the manufacturer of a Serpollet motor of 3 or 4 horse power for launches.

Wanted—Revolutionary Documents, Autograph Letters, Journals, Prints, Washington Portraits, Early American Illustrated Magazines. Correspondence Solicited. Address C. A. M. Box 773, New York.

Inquiry No. 38.—Wanted the name and address of a manufacturer of machine for painting flat surfaces, mouldings, etc., that require painting on one side only.

Inquiry No. 39.—Wanted the name and address of a manufacturer of diving outfits to be used in very shallow water and that do not need an air pump.

Inquiry No. 40.—Wanted the name and address of a manufacturer of sand blast apparatus.

Inquiry No. 41.—Wanted the name and address of a manufacturer who could make a tool of the following description, in quantities: A sharp steel cutting edge with an aluminum handle.

Inquiry No. 42.—Wanted the name and address of a manufacturer of machines for blanching and grinding, or otherwise preparing peanuts.

Inquiry No. 43.—Wanted the name and address of a manufacturer of machinery to make small wooden sticks like match sticks, for the manufacture of Persian shades.

Inquiry No. 44.—Wanted the name and address of a manufacturer of tools and machinery for sheet iron work, such as stamping and folding.

Inquiry No. 45.—Wanted the name and address of a manufacturer of small paper disks about 2 inches in diameter, 7-16 face and 1 1/2 hole, made of compressed paper and used for friction purposes in variable speed pulleys.

Inquiry No. 46.—Wanted the name and address of a manufacturer of feather duster machinery.

Inquiry No. 47.—Wanted the name and address of a manufacturer of water motors; answer stating different sizes made.

Inquiry No. 48.—Wanted the name and address of a manufacturer of machinery for printing on tin.

Inquiry No. 49.—Wanted the name and address of a manufacturer of worm gears, such as are used in cream separators; with full worm instead of one worm and one straight gear.

Inquiry No. 50.—Wanted the name and address of a manufacturer of boiler water tubes with a circulating pipe inside, of copper and brass for model boilers and steel for larger ones.

Inquiry No. 51.—Wanted the name and address of a manufacturer of paraphernalia for side degrees for secret societies, such as trick goats, trick chairs, etc.

Inquiry No. 52.—Wanted the name and address of a manufacturer of machinery for printing postage stamps and like work.

Inquiry No. 53.—Wanted the name and address of a manufacturer of a successful cow-milking machine.

Inquiry No. 54.—Wanted the name and address of a manufacturer of machinery for shaving off the bark of a special foreign tree (name not given).

Inquiry No. 55.—Wanted the address of a factory willing to undertake the manufacture of a new separable collar button in quantities.

Send for new and complete catalogue of Scientific and other Books for sale by Munn & Co., 361 Broadway, New York. Free on application.

Notes & Queries

HINTS TO CORRESPONDENTS.

Names and Address must accompany all letters or no attention will be paid thereto. This is for our information and not for publication.

References to former articles or answers should give date of paper and page or number of question.

Inquiries not answered in reasonable time should be repeated; correspondents will bear in mind that some answers require not a little research, and, though we endeavor to reply to all either by letter or in this department, each must take his turn.

Buyers wishing to purchase any article not advertised in our columns will be furnished with addresses of houses manufacturing or carrying the same.

Special Written Information on matters of personal rather than general interest cannot be expected without remuneration.

Scientific American Supplements referred to may be had at the office. Price 10 cents each.

Books referred to promptly supplied on receipt of price.

Minerals sent for examination should be distinctly marked or labeled.

(8067) C. A. C. writes: I want to make a coil for a jump spark suitable for a gasoline engine. Can you give me any information in regard to it? A. SUPPLEMENT No. 1281, price 10 cents, contains an article upon gas engine ignition. A description of a jump spark coil is given therein which can be made from the description if you understand the general method of doing such work.

(8068) F. L. asks: Does water, when converted into vapor, obey Avogadro's law, and expand so as to equal to the sum of two volumes of hydrogen and one volume of oxygen of which it is composed? A. Water obeys Avogadro's law when in the form of vapor, just as any other vapor does, but its volume is not that of two volumes of hydrogen and one of oxygen. When two volumes of hydrogen and one of oxygen combine to form water, they furnish two volumes of water vapor. There is a shrinkage of one-third in the result. See any good chemistry, such as Remsen's, price \$1.25.

(8069) C. F. De W. writes: What is meant by expansion engines? Also what is meant by high and low pressure engines? If a condensing engine is a low pressure engine, why is it so? A. An expansion engine is any engine in which the steam at full pressure does not follow the piston for the whole stroke, but is cut off at some specified point, allowing the steam to drive the piston to the end of the stroke under a decreasing pressure. "Low pressure engine" is the old name for a condensing engine. High pressure engine is the usual designation of a non-condensing engine running with high pressure. The early low pressure engine used steam at from 7 to 10 pounds pressure and depended upon a vacuum and condenser to add to its work.

(8070) W. G. writes: Kindly state how much voltage is needed to run the motor described in your issue of December 8 last; also state if No. 22 wire will answer just as well to wind the armature as No. 21, which I cannot get? A. The diagram of the motor and its connections shown in the issue of December 15 gives a battery of four cells, two in series and two series in multiple for running the motor. This indicates not more than four volts as needed. No. 22 wire will answer for winding the motor.

INDEX OF INVENTIONS

For which Letters Patent of the United States were Issued for the Week Ending

FEBRUARY 12, 1901,

AND EACH BEARING THAT DATE.

[See note at end of list about copies of these patents.]


Acids, producing chlorides of aromatic sulfonic, A. Bischoff..... 667,861
Alarm apparatus, R. Segerdahl..... 667,958
Alarm system, automatic, F. McGloin..... 667,727
Alcoholic fermentation and recovering the volatile gaseous products, accelerating, A. Graunga..... 668,144
Ammunition hoists, working pawl for, J. Bogel..... 663,083
Angler's book, R. B. Cantrell..... 667,676
Animal trap, C. C. Bowen..... 668,084
Annunciator, station or street, A. H. Poe..... 667,736
Apple picker, W. H. Schroeder..... 667,995
Armpit shield, S. G. McClain..... 667,725
Assaying device, A. Campbell..... 667,969
Axle box, E. D. Ives..... 667,779
Axle box, A. Katona et al..... 667,944
Axle, extensible, P. W. Carney..... 668,091
Axle lubricator, P. Bartlett..... 668,081
Axle lubricator, car, W. N. Sheehan..... 668,059
Axle, vehicle, E. D. Ives..... 667,778
Bailing press, J. Kerns..... 668,129
Basin waste, H. M. Weaver..... 667,834
Battery storage and transfer system, electric, C. O. Mailloux..... 668,109
Battery transfer apparatus, electric, C. O. Mailloux..... 668,108
Beam, truss, W. P. Bettendorf..... 667,667
Bearing, anti-friction, G. Deharde..... 667,684
Bearing, anti-friction, J. E. Norwood..... 667,989
Bearing, vehicle axle, A. D. Block..... 668,082
Bed couch, E. R. Leighton..... 667,916
Belt trap, queen, W. A. J. Simpson..... 667,894
Belt and pulley, driving, A. Steward..... 667,830
Belt holder, D. N. Muir..... 667,918
Berry bushes, apparatus for laying down and covering, W. L. Hawley..... 668,146
Bicycle brake, E. L. Mayer..... 667,887
Bicycle, motor, F. B. Widmayer..... 667,858
Bicycle saddle, M. E. Shane..... 668,056
Blast stop for hot blast valves, J. Scott..... 667,797
Boat draining device, H. J. J. Paff..... 668,119
Boiler, See Steam boiler.....
Boiler or furnace fire box, G. Chantler..... 667,970
Book and support, loose leaf, A. P. Brown..... 667,865
Book, manifold sales, H. H. Norrington..... 668,117
Book, rounding and backing machine, J. Meek..... 668,148

Bookcase, sectional, J. F. Laning..... 667,915
Boot polishing machine, E. Glaser..... 668,147
Bottle cleaning apparatus, C. F. G. Burow..... 667,817
Bottle, mullage, H. W. Scattergood..... 668,053
Bottle nipple, nursing, J. M. Rosegrant..... 667,738
Bottle, non-refillable, J. R. Lynn..... 667,886
Bottle, non-refillable, Netrefa & Schubliesser..... 668,115
Bottle stopper, E. C. Shilling..... 668,061
Bottle stopper, J. & J. H. Whatmough..... 668,029
Bottle stoppering device, P. Samain..... 668,020
Bottle washer, E. Kersten..... 667,709
Bottles, device for preventing refilling of, W. J. Kolts..... 668,105
Box, H. G. Roth..... 667,828
Box, fastening and releasing device, J. Popper..... 668,018
Brake, See Bicycle brake. Electric brake.....
Brake mechanism, H. Sloan..... 667,800
Brake mechanism, electric, F. C. Newell..... 667,729
Bridge or wharf floor construction, J. G. McMillan (reissue)..... 11,889
Bung or stopper, expanding, E. C. Phillips..... 668,120
Burial case, J. F. Lorech..... 668,013
Burner. See Gas burner. Vapor burner.....
Butcher knife and saw, combined, Emery & Stewart..... 667,872
Button, J. W. Treadwell..... 667,748
Button, collar, C. E. Morrison..... 667,888
Cable grip or clutch, M. Drobesch..... 667,688
Cage chair operating mechanism, M. W. Jelinek..... 667,781
Cage chair, safety, M. W. Jelinek..... 667,780
Calendering machine, D. Beswick..... 667,666
Cameras, locking device for lens carriages of, E. R. Bullard..... 668,090
Can cover, creaming, A. H. Stone et al..... 667,895
Car coupling, W. K. Right..... 667,710
Car coupling, G. O. White..... 667,752
Car draft box, E. Posson..... 667,921
Car fender, street, G. W. Gardner..... 667,979
Car grain door, freight, C. D. Norman..... 667,949
Cars, anti-friction center bearing for railway, J. E. Norwood..... 667,991
Cars, anti-friction side bearing for railway, J. E. Norwood..... 667,990
Carding machine feeding mechanism, H. Kemp..... 667,708
Carrier. See Package carrier.....
Cart, ash, C. Brandt..... 667,837
Cart cover, ash, H. A. Dirkes..... 667,931
Cartridge magazine, C. R. Wagner..... 667,856
Cash register, C. A. Lee et al..... 667,843
Casket rough box, J. Schirra..... 667,956
Casting box, L. C. Crowell..... 667,681
Cattle guard, W. R. Allen..... 667,757
Chain link, G. G. Howe..... 667,775
Chain, sprocket, S. F. Clouser..... 667,971
Chair, W. M. Boenning..... 668,125
Chuck for coiling stud spirals, J. R. Uecker..... 667,749
Cigarette machine, Stern & Martin..... 667,802
Clasp and belt holder, W. B. Bruce..... 668,088
Clavier, practice, A. G. Bergman..... 668,003
Clinometer, ship's, F. W. Wood..... 667,836
Clip. See Single tree clip.....
Clock, repeating alarm, A. Bannatyne..... 668,032
Clothes line holder, E. Shaw..... 668,132
Clothes pounder, B. Hines..... 667,703
Clutch, friction, C. Seybold..... 667,798
Coal cutting machine rear jack, D. W. Jones..... 667,823
Cock, stop and waste, W. H. Rawe..... 667,737
Coin controlled meter, Craig & Page..... 667,818
Collar attachment, horse, H. L. Gulline..... 667,696
Collar for horse's neckwear, supporting, C. B. Ellsworth..... 668,040
Combination lock, P. Nash..... 668,049
Communion cups, filling device for individual, T. M. Morrison..... 667,947
Compass deviation finder, A. Lietz..... 667,785
Composition of matter, F. A. Lobert..... 667,786
Conveyer, H. W. Baker..... 668,079
Conveyer, S. B. Peck..... 668,050
Copy holder, R. E. Briner..... 667,763
Copying pad moistener, E. R. Hodges..... 667,704
Corset, C. S. Reed..... 667,922
Cotton chopper, R. F. Patman..... 667,733
Counting device, W. A. Swarn..... 667,804
Crate, W. H. Wright..... 667,755
Crushing rolls, F. M. Iler..... 667,777
Crystallization in motion, apparatus for, A. L. Marshall..... 668,110
Cuff holder, E. E. Hawkins..... 667,941
Cultivator, D. E. Barton..... 668,124
Cultivator, W. Skakel..... 667,740
Cultivator and harrow, N. R. Garret..... 667,839
Cultivator shield, corn, Bond & Skelton..... 668,136
Cultivator shovel cleaner, W. Skakel..... 667,741
Curette, C. W. McDade..... 667,726
Curtain fastener, W. Fetzner..... 667,873
Curtain pole, Kerr & Perrine..... 667,982
Curtain roll hanger, adjustable, E. F. Kaiser..... 667,943
Curtain stretcher, J. A. Gemmill..... 668,126
Curtain stretcher and quilting frame, S. E. Lincoln..... 667,845
Cutting knife for machines, F. Kraus..... 667,715
Cutting tool, C. P. Mingst..... 667,987
Desk, hotel register, J. D. Mets..... 667,826
Diffusion cells, locking device for, J. Taylor..... 667,747
Dish washer, E. Brady..... 667,670
Disinfecting and fumigating apparatus, J. H. Semmes..... 668,055
Display box, P. A. Becker..... 667,815
Display tray, barrel cover, S. H. Klein..... 667,761
Door check, E. Blamey..... 667,761
Door lock and alarm, portable, A. L. Shore..... 667,675
Double acting press, A. C. Campbell..... 668,099
Draw bar rigging, C. W. Heishley..... 668,078
Drawer support, anti-friction, H. F. Baker..... 667,866
Drawing press, A. Calleson..... 668,137
Drill, Bradley & Stonehouse..... 667,848
Driving mechanism, H. W. Morgan..... 667,848
Dye and making same, violet black azo, Ems & Schirrmacher..... 667,935
Dye, making black substantive sulfor, Elbel & Rosenberg..... 667,689
Dyeing, etc., apparatus for, J. Major..... 667,825
Dynamometer, bicycle, C. A. Perkins..... 667,920
Eaves strip, W. A. Fingles..... 667,821
Electric brake, F. C. Newell..... 667,730
Electric spark coil, S. B. Morss..... 667,889
Electric switch, D. R. Bruce..... 667,764
Electromotors, means for stopping, J. J. Wood..... 668,030
Elevating and conveying apparatus, J. M. Dodge..... 667,975
Engine igniting device, hydrocarbon, J. W. Packard..... 667,792
Engine mixer and vaporizer, explosive, Hatcher & Packard..... 667,910
Engine piston, explosive, W. O. Worth..... 668,075
Engine speed regulator, explosive, W. A. Hatcher..... 667,908
Engines off dead centers, mechanism for moving, C. F. Rigby..... 667,993
Eraser holder and pencil attachment, F. Oelke..... 667,950
Explosion and combustion motor, W. Maybach..... 668,111
Explosion engine or motor, S. Miller..... 667,846
Eyeglasses, C. E. & A. B. Loose..... 667,787
Eyeglasses or pince-nez, E. J. Schweizer..... 667,997
Fabric. See Felt boot fabric.....
Fabric, C. Green..... 668,010
Fabric, composition for use in treating textile, C. Green..... 668,011
Fabrics, composition for use in treatment of textile, C. Green..... 668,145
Fan propulsion, C. Adelhelm..... 667,899
Fastener, A. F. Fisher..... 667,874
Fastening device, metal, G. G. Wyland..... 667,814
Feeder, automatic boiler, W. Cunningham..... 668,008
Feeder, calf, H. B. Smith..... 668,062
Fender. See Car fender.....
Felt boot fabric, R. Henton..... 667,699
Fertilizer distributor, W. C. Temples..... 668,026
File, L. C. McNeal..... 668,114
File for manuscripts, music, etc., indexed, Gillrath & Giers..... 668,097
Filter, water, G. F. Hodgkinson..... 668,127
Fire escape, J. Stone..... 667,803
Fireproof building structure, J. O. Ellinger..... 667,871
Fish hook, W. A. Strong..... 668,066
Fishing device, W. Dwigans..... 667,932
Floor sawing and rabbeting machine, Gardner & Abbott..... 667,978
Flue scraper, V. Radspinner..... 668,122
Flue stopper, J. Kirkwood..... 667,883
Fluid pressure regulator, Croslen & McMillen..... 668,094
Flushing apparatus, W. P. Hastings..... 667,87

Food heating and serving apparatus, A. C. Cornell..... 668,036
Food or bread, apparatus for manufacturing cereals into forms of, H. D. Perky..... 667,892
Fountain. See Watering fountain.....
Fruit picker, C. G. Morris..... 667,988
Furnace. See Hot air furnace.....
Furniture, composite, F. J. F. Kohlmann..... 667,983
Game board, H. Toaspen, Jr..... 668,027
Gas burner, H. Hinckley..... 667,702
Gas burner antivibratory support, J. Franklin..... 668,042
Gas cut off, R. Wynell..... 667,756
Gas generating apparatus, acetylene, D. McDonald..... 667,919
Gas generator, acetylene, Charbeneau & Schaldenbrand..... 667,766
Gas generator, acetylene, W. G. Murphy..... 667,724
Gas generator, acetylene, Sober & Porter..... 667,801
Gas manufacturing apparatus, H. A. Bradley..... 667,864
Gas producer, W. Swindell..... 667,925
Generator. See Gas generator. Steam generator.....
Grinder, clipper, W. Taber..... 667,960
Hame fastener, J. Hausman..... 668,098
Hammer, pneumatic, J. Boyer..... 667,863
Hammer, pneumatic, J. K. Lencke..... 667,784
Handle bar, P. Oftedahl..... 667,732
Handle bar supporter, C. Maldaner..... 667,716
Hatchet, W. Innes..... 668,046
Hay rake attachment, horse, E. C. Herbert..... 667,841
Hinge, J. F. Collins..... 667,838
Hinge, lock, R. Roscow..... 667,851
Hog nose ring, N. W. Marshall..... 667,717
Holtfast, H. N. Brown..... 667,816
Horse breaking apparatus, J. Craig..... 667,978
Horse checking device, E. C. Eaglesfield..... 667,976
Hot air engine, F. Stolze..... 667,744
Hot air furnace, J. T. & T. R. Brien..... 667,671
Hub, wheel, Macculloch & Gash..... 667,984
Humidifier, R. C. Ulrich..... 668,028
Hydrant cap and pipe coupling, multipart, R. D. Tackaberry..... 667,808
Ice cream freezer driving mechanism, C. Hillert..... 668,100
Ice manufacture, apparatus for deaerating water in, E. J. Ulrich..... 667,897
Indicator. See Paper thickness indicator.....
Inking apparatus, T. M. North..... 667,731
Insulator, feeder wire, C. K. King..... 667,882
Ironing table, W. N. Beyer..... 667,668
Ironing table, O. O. Stageberg..... 668,064
Jack. See Shoemaker's jack.....
Jar cap, R. W. Booth..... 668,005
Jar covers, device for truing fruit, Headman & Curtis..... 667,942
Joint for shade rollers, etc., W. Sparrow..... 668,063
Key and automatic stop cock, combination, Randall & Holden..... 667,952
Knitting machine stripping attachment, D. F. Sullivan..... 668,025
Knot pin, J. M. Semples..... 667,829
Lace fastener, shoe, H. A. Frye..... 667,939
Lace fastener, shoe, C. H. Guerin..... 667,683
Ladder, P. W. Wells..... 667,927
Lamp, acetylene, J. J. Hendler..... 667,774
Lamp chimney guide, F. Altmann..... 667,964
Lampblack making apparatus, Houze & Dhe..... 668,045
Lantern, J. R. Gilbert..... 668,096
Last making machine, E. A. Eastman..... 667,934
Last sawing machine, E. A. Eastman..... 667,933
Latch, spring, L. Scofield..... 667,796
Lathate center lubricator, P. Schwellkart..... 667,957
Lathate feeding mechanism, turret, W. L. Schellenbach..... 667,994
Lathate operating device, turret, J. W. Brown, Jr..... 668,086
Lathes, taper attachment for metal working, J. D. Hazlet..... 667,912
Leather, manufacture of artificial, G. S. & C. Falkenstein..... 667,770
Leather stretching machine, P. H. Croul..... 668,037
Life saving ladder, J. Whiteley..... 667,753
Link holder, C. Stephenson..... 667,998
Liquor mixer and dispenser, G. Neudecker..... 667,891
Locking attachment for doors, shutters, etc., J. B. Anderson..... 668,031
Locomotive sander, pneumatic, J. G. Neuffer et al..... 667,948
Loom attachment, E. S. Stimpson..... 668,024
Loom harness, P. A. Wagner..... 667,812
Loom shuttle, J. T. Ahrens..... 668,123
Loom shuttle changing motion, B. Crossley..... 667,767
Loom temple, E. S. Stimpson..... 668,133
Lubricator. See Axle lubricator. Lathate center lubricator.....
Lubricator, E. L. Seibert, Sr..... 668,054
Mattress filling machine, G. G. Fuchs..... 667,693
Mattress support, C. L. Friederichs..... 667,938
Medicinal vaporizer, C. B. Tefft..... 667,961
Metal forming machine, H. L. Gulline et al..... 667,697
Metal working machine, Hinckley & Anderson..... 667,880
Milk heater, E. Taage..... 667,809
Mill. See Windmill.....
Miter box, J. H. Matson..... 667,917
Molding clay, etc., apparatus for, Rowley & Till..... 667,954
Molding composition, H. Elmquist..... 668,095
Mop wringer, J. H. Johnson..... 668,102
Mopping implement, floor, A. S. Mathers..... 667,985
Motor, See Explosion and combustion motor.....
Motor, L. Berger..... 668,002
Motor, J. R. Daniels..... 667,683
Motor, H. F. Shaw..... 668,058
Mowing machine, M. Jewell..... 667,706
Multiple piston engine, C. H. Benton..... 667,760
Musical instrument, stringed, M. Shelton..... 668,060
Musical instruments, tuning device for stringed, E. B. Brandon..... 668,138
Nail grip, H. B. Alliger..... 667,663
Nitrocellulose or similar substance and making same, D. Bachrach..... 667,759
Nursery or toilet chair, folding, N. P. Meade..... 667,986
Nut lock, W. R. Allen..... 667,758
Optometer, A. J. Cross..... 667,973
Package carrier, F. J. Hanchett..... 667,906
Pail, wooden, J. H. Taylor..... 667,831
Paper, etc., machine for making, Case & Gray..... 667,902
Paper making machine, Tompkins & Barnes..... 668,068
Paper thickness indicator, C. Beckh..... 667,665
Paper tube winding roller, H. F. Loscher..... 668,107
Pegging machine, J. E. Bickford..... 667,860
Pegging machine horn, J. E. Cickford..... 667,928
Pencil holder, J. F. Call..... 667,968
Piano, mandolin, banjo and guitar attachment, T. P. Cook..... 667,972
Piano trap work, G. H. Fox..... 668,143
Pile driver, S. H. Blowers..... 667,669
Pin. See Knives.....
Pin holder, M. Burkart..... 667,673
Pin cutting tool, A. E. A. Wathler..... 667,857
Pipe wrench, F. E. Sands..... 667,852
Planter, corn, Althaus & Hesselmann..... 667,900
Plate accessory, child's, G. Bergwitz..... 668,004
Plate and stove lid lifter, combined, H. M. Evenstad..... 667,691
Ploow point, detachable, C. A. Weimer..... 668,006
Ploow subsoil attachment, R. T. Miller..... 668,113
Plumber's appliance, H. N. Kirk..... 667,913
Poke, animal, Specht & Ticken..... 667,959
Postmarking and stamp canceling machines, feed mechanism for, J. E. Wright..... 667,754
Potato digging machine, C. J. Moulton..... 667,890
Potato sorter, E. Taylor..... 667,746
Printer's chase, C. E. Miller..... 667,946
Printer's galley, C. J. Blair..... 667,862
Printer's quoin, E. L. Wilson..... 668,072
Printing device, hand, F. B. E. Unger..... 668,069
Printing device, ticket, A. A. Bryan..... 667,672
Printing machine envelop, Clymer & Wiegand..... 668,035
Printing machines, automatic apparatus for feeding sheets of paper to, M. Koenig..... 667,714
Printing press, L. C. Crowell..... 667,679
Printing press, A. Reid..... 667,923
Printing press feed attachment, T. L. Cannon..... 667,765
Printing press throw off attachment, S. Halvorson..... 667,672
Printing upon round objects, machine for, R. B. Kirkwood..... 668,104
Projectile throw mechanism, J. H. Cook..... 667,867
Pulverizer, plover, A. Anderson..... 668,001
Punching apparatus, Tucker & Pross..... 667,926
Quill retaining device, A. B. Morse..... 667,849
Rail coupling, W. W. Luger..... 667,945
Rail joint, W. H. Brown..... 667,901

Railway, closed conduit electric, L. Dion..... 667,904
Railway, elevated electric, L. A. Brown..... 667,966
Railway joint, J. H. Dickinson..... 667,685
Railway or tramway vehicles, hydraulic brake for, C. Durey..... 667,819
Railway switch, street, W. A. Clapp..... 668,092
Railway tie, composite, C. C. Harrell..... 667,698
Railway ties and switches, cleaning and setting tool for, H. Thompson..... 667,855
Razor strop, H. B. Emerson..... 667,905
Recorder. See Ship speed recorder. Time recorder.....
Reel holder, D. L. Murchison..... 667,788
Refrigerator car, L. K. Bohm..... 668,033
Relay, signal controlling, H. E. Shreeve..... 668,022
Respirator, S. Guthrie..... 667,840
Rheostat and circuit breaker, H. B. Cutter..... 668,140
Ring. See Hog nose ring.....
Rock drilling machinery, R. L. Ambrose..... 667,664
Rock, platform or base, W. I. Bunker..... 667,967
Rod or wire mill reeling or coiling device, V. E. Edwards..... 667,870
Rosette, W. T. Thomas..... 668,134
Rotary engine, J. Knowles..... 667,713
Rubber soles to bottoms of leather boots or shoes, machines for applying, G. F. Butte..... 667,674
Rule and level, plumb, J. Morrison..... 668,015
Rule, dressmaker's, C. Schierbaum..... 667,739
Sash holder and fastener, W. J. Russell..... 668,052
Sash, window, C. D. Tabor..... 667,745
Saw sharpening machine, Schofield & Filstrup..... 667,924
Saw sharpening machine, automatic, W. G. Buhl..... 668,089
Sawing machine, E. Pollard..... 667,793
Seacold bracket, H. A. Patzold..... 667,992
Scissors, tool, F. W. Klever..... 667,914
Screw, jack, R. B. Allison..... 668,077
Seat for outdoor use, J. H. Hunter..... 667,776
Sewing machine, buttonhole, R. S. Kelso..... 667,824
Sewing machine stitch separator, P. Couture..... 667,677
Sewing machine take up, H. A. Klemm..... 667,712
Sewing machine, waxed thread, W. L. Johnson..... 668,047
Shade and curtain bracket, S. D. Dilts..... 667,930
Shaft coupling, A. C. Pessano..... 668,017
Ship speed recorder and course indicator, A. Bopp..... 667,762
Shoemaker's jack, S. Carlsen..... 668,139
Signaling apparatus, W. A. Swarn..... 667,805
Silicon and hydrogen, compound of, C. B. Jacobs (reissue)..... 11,888
Singletree clip, F. E. Lack..... 667,884
Skirt lifter, R. J. Piper..... 668,121
Smoke in furnace, apparatus for consuming, J. R. Untiedt..... 667,750
Smoothing machine, F. A. Stroeter..... 667,896
Soldering compound, E. M. Totten..... 667,999
Speed mechanism, variable, H. C. Warren..... 668,135
Spike, T. J. W. Hick..... 667,700
Spinning frame stop motion, W. G. Eaton..... 668,039
Spinning roll weight levers, lever screw for holding, H. A. Owen..... 668,131
Splint, R. de Puy..... 667,768
Spool holder, H. E. Smith..... 667,742
Sprayer, fruit tree, F. L. Capps..... 668,007
Stacker, pneumatic straw, T. Goodale..... 667,694
Stacker, wind, W. W. Dingee..... 668,141
Stair pad, J. J. Hinde..... 668,101
Stamp destroyer, revenue, Monroe & Brencle..... 668,014
Stamp, hand, L. K. Scottford..... 668,021
Stamp or label affixing machine, W. P. Goebel..... 667,822
Steam boiler, D. G. Frank..... 667,400
Steam boiler, C. D. Moberg..... 667,718
Steam generator, H. Braby..... 668,006
Steering mechanism for ships or vehicles, G. A. Long..... 668,106
Stoker, mechanical, J. W. Kincaid..... 668,130
Stone boring machine, S. Messrobian..... 668,112
Stone surfaces, ornamenting polished, A. Wilcke..... 667,898
Stopper. See Bottle stopper. Flue stopper.....
Stopping device, W. Finn..... 667,936
Stove door screen, H. E. Fine..... 667,692
Strainer, C. H. Kopley..... 667,782
Sugar boiling, J. & C. McNeil..... 667,850
Supporter, combination, C. C. Lantz..... 667,783
Surgical chair, C. F. Davidson..... 668,169
Suspenders, F. W. Ostrom..... 668,118
Switch bar, adjustable, C. Partington..... 667,827
Table machine, E. V. Pechin..... 668,016
Tackling machine, F. McJolin..... 667,728
Tank heater, J. R. Kirkpatrick..... 667,711
Telegraph, ship's, F. W. Wood..... 667,859
Telephone switchboard and circuit, Gilman & Herzog..... 668,044
Tension device, Van Patten & Hill..... 668,070
Terminal socket, E. W. G. Hoffmann..... 667,980
Thresher and separator, grain, P. Habeger..... 667,876
Threshing machine, E. W. Flagg..... 668,041
Threshing, separating and cleaning peas, beans, etc., mechanism for, C. F. Stone..... 668,023
Tie. See Railway tie.....
Time recorder, Workman's, J. Gardam..... 667,771
Tire setter, M. A. Patton..... 667,734
Tire setter, rubber, R. O. Stutsman..... 668,067
Tires, device for automatically inflating pneumatic, A. G. T. Overstrom..... 667,791
Tires, mixture for healing punctured, D. Mulqueen..... 667,722
Tongue or pole socket, C. Vanarsdall..... 667,900
Tool holder, C. Pease..... 667,735
Tool post, J. B. Haines..... 667,877
Tooth, artificial, F. A. L. Murdock..... 667,723
Torpedo, railway, W. W. Weaver..... 667,813
Toy, T. N. Waller..... 667,751
Toy bank, registering, J. Schade, Jr..... 667,955
Toy, spinning, E. W. Risbrough..... 667,794
Transformer, Scawedtmann & Layman..... 667,996
Trap. See Animal trap. Bee trap.....
Trays, packing, J. McCauley..... 668,048
Trolley mechanism, J. H. Cook..... 667,868
Trolley switch, C. P. Cornell..... 667,903
Trolley wheel, Shaughnessy & Thomas..... 668,057
Trousers protector, C. L. Puffer..... 668,051
Trunk lock, G. F. Harrison..... 667,907
Tubes, manufacturing seamless, S. E. Diescher..... 667,687
Tubing, apparatus for manufacturing seamless, S. E. Diescher..... 667,686
Tuffing machine, pad, D. E. Bowler..... 667,795
Tungstake's making, Holloway & Lake..... 667,705
Turning wooden bobbins, machine for, R. W. Jorres..... 667,981
Twine holder, W. G. Esch..... 667,769
Twisting machine, J. E. Tynan..... 667,811
Twisting machine stop motion, J. E. Tynan..... 667,810
Type making machine, P. G. Nuernberger..... 667,790
Typewriters, combined indicator and paper holder for, E. H. Eldredge..... 667,690
Typewriting machine, L. S. Burdige..... 667,929
Typewriting machine, E. Heath..... 667,773
Umbrella rib, W. E. Moulton..... 667,719
Umbrella rib and stretcher joint, W. E. Moulton..... 667,720
Umbrella stick, W. E. Moulton..... 667,721
Valve, automatic cut off, R. E. Vail..... 667,963
Valve, flushing, W. J. Pine..... 667,951
Valve, globe or other, N. C. Locke..... 668,015
Valves, protecting device for spring pressed, H. Stein..... 668,065
Vapor burner, J. A. Demson..... 667,974
Vehicle attachment, motor, B. E. Dakin..... 668,009
Vehicle frame, motor, Hatcher & Packard..... 667,909
Vehicle, motor, W. A. Hatcher..... 667,911
Vehicle, motor, W. O. Worth..... 668,073
Vehicle, motor, W. O. Worth..... 668,074
Vehicle, road, C. A. Immler..... 667,881
Vehicle running gear, Garrels & Kimball..... 667,875
Vehicle steering mechanism, H. S. Ingalls..... 667,842
Vessels at sea, apparatus for coaling, J. E. Walsh..... 668,071
Voting machine, G. W. Crozier..... 667,802
Voting machine, W. A. Swarn..... 667,806
Wagon, dumping, G. Kautz, Sr..... 667,707
Wagon seat, adjustable, H. Duhamel..... 668,038
Wall bracket and scaffold frame, S. Jessup..... 668,128
Warp machine, circular, H. Hill..... 667,701
Washer. See Bottle washer. Dish washer.....
Watering fountain, automatic stock, J. N. McGuire..... 667,789
Weighing and sorting machine, G. F. Englemann..... 667,977
Weighing device, box with connected, S. Weiss..... 667,835
Wheel attachment, E. C. Fremaux..... 667,937

(Continued on page 125)



"Star" Lathe
Foot and Power
Screw Cutting
Automatic Cross Feed
FOR FINE, ACCURATE WORK
Send for Catalogue B.
SENeca FALLS MFG. CO.
695 Water Street,
Seneca Falls, N. Y., U. S. A.

ARMATURE WINDING, RIGHT AND LEFT HANDED.—An important paper for all amateurs. 17 illustrations. SCIENTIFIC AMERICAN SUPPLEMENT, No. 1139, price 10 cents. For sale by Munn & Co. and all newsdealers. Send for catalogue.

ENGINE & FOOT MACHINE SHOP OUTFITS, LATHES, TOOLS AND SUPPLIES.
SEBASTIAN LATHE CO. CINCINNATI, O.

Tells About Tools

A perfect encyclopedia of tools in use in every trade and profession with prices and discounts of same.

Montgomery & Co.'s Tool Catalogue.


510 pages, well printed. Copiously illustrated. A valuable book of reference for everybody interested in tools or machinery. Mailed for 25 cents, sent to MONTGOMERY & CO., 105 Fulton St., New York City.

There is never any question about the quality of a

B. F. BARNES UPRIGHT DRILL.

The tool here illustrated is our 20-inch Drill, and we guarantee it to drill up to 1 inch in steel and 1 1/2 inch in cast iron at a good rate and without strain. We build larger sizes and will be glad to send full data on our entire line to interested people.

B. F. BARNES CO., Rockford, Ill.





LATHES
FOR
GUNSMITHS, TOOL
MAKERS, EXPERI-
MENTAL AND REPAIR
WORK, ETC.
Send for Illus. Catalog.
W. F. & Jno. Barnes Co.
1999 Ruby Street,
Rockford, Ill.

\$1 YEARLY FOR REPAIRS.

It has been found that it costs a trifle less than \$1 per year to keep our **Holsting Engines** in repair. That speaks well for their superior make and durability, doesn't it? There is no more economical or serviceable engine made for mines, quarries, docks, etc. Much cheaper than steam. Both friction and gear oil 6 to 150 h. p.

Weber Gas & Gasoline Engine Co., P. O. Box 1114-a, Kansas City, Mo.




New Microscope for Nature Study
and for use in the Examination of Ores, Metals, Woods, Fibre, etc.

Queen Acme No. 6 with 1 Ocular and 1 in. objective giving power of about 100 diameters, 1 set of 12 prepared slides of insect parts and other interesting specimens, all in case, \$16.00. Ask your nearest Optician for it.

QUEEN & CO., Inc.
Optical and Scientific Instrument Works,
1010 Chestnut St., Phila., Pa.
59 Fifth Ave., New York.

Write for Circular.

THE BICYCLE: ITS INFLUENCE IN Health and Disease.—By G. M. Hammond, M.D. A valuable and interesting paper in which the subject is exhaustively treated from the following standpoints: 1. The use of the bicycle by persons in health. 2. The use of the bicycle by persons diseased. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 1002. Price 10 cents. To be had at this office and from all newsdealers.



A Marvelous Machine!

Watch the wonderful work done by our **Apex Nipple and Pipe Mill Machine**. Threads nipples of all sizes. So swiftd that it can be reversed and pipe cut off close to grippers. Vise can be opened or closed while machine is in motion. Send for Catalogue.


THE MERKEL MFG. CO., 501 Curtiss Street, Toledo, Ohio.

Acetylene Gas Lighting

Reduced to the most Efficient, Safest, Simple and Economical Use.

We guarantee our machines perfectly automatic in action, to extract all the gas from the carbide, and absolutely no over production or loss of gas. Approved by the various Boards of Fire Underwriters. Standard sizes 10 to 50 lights. Exclusive territory given to responsible agents. Correspond with:

NIAGARA FALLS ACETYLENE GAS MACHINE CO.,
Niagara Falls, N. Y. and Canada.





THE AUTO-CARBURETTOR
made upon a new principle furnishes a reliable explosive mixture. Easy ignition and greatest expansion. No pump required. Uses any grade of gasoline with no waste. Especially adapted to automobile and cycle motors. Our customers say it is the best Carburettor in the market. We make also the **Register Valve** for controlling the flow of gasoline or other fluids. Write us for prices and booklet on Carburettors.

THE AVERY & JENNESS CO.,
30 W. Washington St., Chicago, Ill.

THE JOHNSON ROTARY PUMP.
Simple of construction, positive in action, easy and quiet in operation. Especially adapted to pumping soap, oil, sugar, lard, glucose, acids, starch, glue, varnish, corn and water, malt, etc. Large sizes for irrigation.

Made as a belt or steam pump, or combination, or operated by electric motor or gasoline engine. Manufactured by

DAVIS-JOHNSON CO., Station V, CHICAGO, ILL.
James H. Robley, Agent, 95 Liberty St., N. Y. City.



Wheels, detachable tread shoe for vehicle, Worth & Donaldson.....	668,076
Wheels, making up tension, A. A. Tisdale.....	667,962
Winding machine, V. G. Hazard.....	667,879
Winding machine, T. H. Savory.....	667,833
Windlass, D. B. Conchus.....	668,003
Windmill, T. S. Barvis.....	667,905
Window locking device, M. E. Reid.....	668,019
Wire splicer, E. Figueredo.....	668,142
Wire stretcher, C. E. Fry.....	668,043
Wire-working tool, N. J. Tate.....	667,854
Wood-preserving apparatus, C. Tschurl.....	667,832
Wooden vessel, G. Ross.....	667,953
Wood-working machine, H. W. Morgan.....	667,847
Wrench, C. H. Noble.....	668,116
Wrench, T. E. Smythe.....	667,743
Yeast-manufacturing apparatus, E. Barbet.....	668,080
Yoke center, neck, F. E. Lack.....	667,885

DESIGNS.

Automobile frame socket piece, H. M. Wells.....	34,071
Bag, leather chataleine, L. Sanders.....	34,066
Bicycle handle bar, E. McCoy.....	34,072
Bicycle saddle, B. F. Wheeler.....	34,073
Bottle, M. Rheinbauer.....	34,062
Bottle, mullage, H. W. Scattergood.....	34,061
Box blank, C. Engberg.....	34,064
Bracket, W. M. Shrader.....	34,083
Buckle, halter, C. H. Thorp.....	34,068
Button, J. D. Phillips.....	34,078
Candy tray, E. W. Crane.....	34,065
Cockey, T. J. D. Fairhurst.....	34,070
Curtain pole holders, bracket or support for, R. H. Beck.....	34,082
Door stop, double, J. M. Hansen.....	34,080
Eyeglass case, W. Zorber.....	34,056
Flower stand, J. Beck.....	34,091
Fumigator stand supporting card, J. W. Castle.....	34,057
Hame attachment, R. Dodson.....	34,089
Harness rosette, G. W. Moore.....	34,067
Hinge, H. T. Bush.....	34,078
Hook, W. H. Benham.....	34,059
Incaudescant mantle support, M. Herskovitz.....	34,086
Lamp, etc., incandescant gas arc, L. T. Alton.....	34,087
Lawn roller handle, R. W. Whitelhurst.....	34,075
Lever handle, C. Morrill.....	34,074
Mugs, blank for imitation, O. E. Fick.....	34,063
Paper clip, C. W. Mowen.....	34,060
Pliers, etc., member for, E. C. McClary.....	34,077
Plovers, etc., brace for eveners and equalizers for, J. T. R. Green.....	34,076
Sewing machine presser foot, leather, G. L. Pierce.....	34,085
Silversmith's stock, P. J. Gordon.....	34,054
Spoons, forks, etc., handle for, W. A. Jameson.....	34,055
Stool pedestal, piano, P. H. York.....	34,089
Stove, W. V. Robinson.....	34,088
Table, F. Voletto.....	34,060
Telephone stand bracket, R. V. Griggs.....	34,084
Tone modifier, F. B. Brock.....	34,092
Window screen drum, roller, E. B. Crocker.....	34,081

TRADE MARKS.

Alcoholic liquors, certain named, Highland Bottling Company.....	35,896
Brushes, Florence Manufacturing Company.....	35,882
Butter, Bartram Bros.....	35,902
Cigars, cigarettes, and smoking tobacco, Porto Rican-American Tobacco Co.....	35,893
Clothing, outer, Treacy, Morris & Co.....	35,877
Fabrics, certain named, L. Dinkelspiel & Sons.....	35,880
Flour, wheat, L. M. Paschall.....	35,900
Food, albuminous nourishing, Dr. Lilienfeld & Co.....	35,899
Hair tonic, F. K. Jones.....	35,884
Insect poison, Jenkins Bros.....	35,883
Iron hollow ware, wrought, Herman Wuppermann Gesellschaft mit Beschränkter Haftung.....	35,905
Laxative compounds, liquid, California Fig Syrup Co.....	35,885
Liment, and Miller.....	35,890
Meats, cured, T. M. Sinclair & Co.....	35,903
Photographic lens, wide angle, L. J. R. Holst.....	35,881
Purgative compounds, liquid, California Fig Syrup Co.....	35,886
Remedy, rheumatic, Wright Medicine Company.....	35,889
Rubber boots and shoes, Apsley Rubber Company.....	35,879
Sugar and sirup, Glucose Sugar Refining Co.....	35,898
Suppositories, F. Fuller.....	35,888
Underwear, silk, F. C. Savage.....	35,878
Whiskies, Slater, Rodger & Co.....	35,897
Wines and liquors, Goldberg, Bowen & Co.....	35,895
Wines, white, E. Kressmann & Co.....	35,894

LABELS.

"Baldwin's Waterproof Blacking," for shoe blacking, I. Baldwin.....	8,116
"Bull Fight," for popcorn, Goodman Produce Company.....	8,117
"First Shot," for shoes, Richardson Bros. Shoe Company.....	8,115
"For a Tooth Ache Wood's Compositum," for a medicine, C. Napoli.....	8,129
"Frank Jones Brewing Co. Ltd. Homestead Ale," for ale, Frank Jones Brewing Company.....	8,121
"Frank Jones Brewing Co. Ltd. India Pale Ale," for ale, Frank Jones Brewing Company.....	8,122
"Frank Jones Brewing Co. Ltd. Nourishing stout," for porter, Frank Jones Brewing Company.....	8,123
"Golden Peacock," for tea, Milliken, Tomlinson Company.....	8,118
"H-S-Ke," for a disinfectant and deodorizer, H-S-Ke Chemical Co.....	8,131
"L. Brunswick, the L B Cure," for a medicine, L. Brunswick.....	8,128
"Niagara," for hams, A. E. von Cotzhausen.....	8,126
"Opalescent Apple," for nursery stock, McNary & Gaines.....	8,132
"Palace Block," for coal, Salt Fork Coal Mining Company.....	8,133
"Rex," for cured meats, A. E. von Cotzhausen.....	8,127
"Runnymede Pure Rye," for whisky, R. F. Balke & Co.....	8,120
"Sore Remedies," for a medicine, L. W. Sauer.....	8,130
"Superba," for coffee, Milliken, Tomlinson Company.....	8,119
"The Life Line of Health," for bottled beer, A. von Cotzhausen.....	8,124
"The Life Preserver," for infant and medicinal foods, A. von Cotzhausen.....	8,125

PRINTS.

"Dr. Pierce's 2 Sheet Rough Rider," for a medicine, R. V. Pierce.....	302
"Fluffed Rugs," for rugs, Ann Arbor Fluff Rug Co.....	300
"Ramon's Brownie Calendar," for medicines, Brown Manufacturing Company.....	301


A printed copy of the specification and drawing of any patent in the foregoing list, or any patent in print issued since 1863, will be furnished from this office for 10 cents. In ordering please state the name and number of the patent desired, and remit to Munn & Co., 361 Broadway, New York.

Canadian patents may now be obtained by the inventors for the inventions named in the foregoing list, provided they are simple, at a cost of \$45 each. If complicated the cost will be a little more. For full instructions address Munn & Co., 361 Broadway, New York. Other foreign patents may also be obtained.



"Profitable Poultry Keeping"
IN ALL ITS BRANCHES. This is the title and theme of our new Year Book. Contains 192 pages, 8x11 in., 200 new and original illustrations of best poultry farms, buildings, etc. in the country. Deals with every phase of the poultry industry in an instructive and profit bringing way. Treats also of the famous non-moisture, self-ventilating and regulating **CYPHERS INCUBATORS**, hatch any other in three or more tests or money refunded. Sent for 10c in stamps. Ask for book 134 Circular and prices free. Address nearest office. **CYPHERS INCUBATOR CO., Boston, Mass., Weyland, N. Y., Chicago.**

GOLD MEDAL PARIS Exposition, 1900



Handsome Illustrated Catalogue mailed on request

UNDERWOOD

Visible Writing, Universal Keyboard, Speed, Touch.
WAGNER TYPEWRITER CO.
189 Monroe St., Chicago. 218-220 B'way, New York.
526 Twelfth St., N. W., Washington, D. C.

The Typewriter Exchange



136 Barclay St., NEW YORK
124 La Salle St., CHICAGO
38 Bromfield St., BOSTON
817 Wyandotte St., KANSAS CITY, MO.
209 North 9th St., ST. LOUIS, MO.
432 Diamond St., PITTSBURGH, PA.
3 West Baltimore St., BALTIMORE, MD.
536 California St., SAN FRANCISCO, CAL.
We will save you from 10 to 50% on Typewriters of all makes. Send for Catalogue.

GUYER'S PATENT DESULPHURIZING FURNACE.




Latest, Cheapest and Best.
Takes the place of Heap or Stall Roasting.
Saves time and money.
Write for particulars.
HENRY GUYER, Casilla 514 LIMA, PERU, S. A.

MORROW COASTER BRAKE.
FITS ANY CYCLE 100,000 IN USE
ADDS PLEASURE AND SAFETY—ALL DEALERS SELL THEM.
RIDE 50 MILES—PEDAL ONLY 35. ECLIPSE MANUFACTURING CO., BOX X, ELMIRA, N.Y.




HIGHEST EFFICIENCY
attained in the
STOVER GASOLINE ENGINE
The best is always cheapest. Write for prices.
STOVER ENGINE WORKS, FREEPORT, ILL.




ROTARY PUMPS AND ENGINES.
Their Origin and Development.—An important series of papers giving a historical resume of the rotary pump and engine from 1588 and illustrated with clear drawings showing the construction of various forms of pumps and engines. 38 illustrations. Contained in SUPPLEMENTS 1109, 1110, 1111. Price 10 cents each. For sale by Munn & Co. and all newsdealers.

THE MIETZ & WEISS KEROSENE and GAS Engine
burns KEROSENE cheaper and safer than gasoline. Automatic, simple, reliable. No electric battery or flame used. Perfect regulation. Belted or directly coupled to dynamo for electric lighting, charging storage batteries and all power purposes.
Send for Catalogue.
A. MIETZ & CO., 128-138 MIETZ ST., NEW YORK. Markt & Co., London, Hamburg, Paris




The "Wolverine" Three Cylinder Gasoline Marine Engine.
The only reversing and self-starting gasoline engine on the market. Lightest engine for the power built. Practically no vibration. Absolutely safe. Single, double and triple marine and stationary motors from 2 to 30 H. P.
WOLVERINE MOTOR WORKS, Grand Rapids, Mich.



LETTER MAKING OF LONG AGO
WAS CRUDE
INDICED
COMPARED WITH
PRESENT DAY
POSSIBILITIES
WHEN THE
SMITH PREMIER TYPEWRITER
IS USED.
IT MARKS THE
HIGHEST POINT
PERFECT
MACHINES
CATALOGUE FREE
SMITH PREMIER TYPEWRITER
SYRACUSE, N.Y.



HOLD ON THERE!
Send 3c. for catalog of
Monarch Marine Gasoline Engines.
3/4 to 45 H. P. \$300 up.
Grand Rapids Gas Engine & Yacht Co., Grand Rapids, Mich.




THE TIRE PROBLEM
has been solved for the rider who has G & J Tires on his wheel. They have the life, elasticity and easy riding qualities of all other good tires, and when punctured are easier to mend. Detach from rim, repair the leak, go on your way rejoicing. No plugs, perspiration or profanity. Simple, isn't it? And it's just as easy as it sounds.
G & J TIRE CO., Indianapolis, Ind.



CANFIELD COASTER BRAKE
EVERY BRAKE FULLY GUARANTEED
ADDRESS—CANFIELD BRAKE CO.
CORNING, N.Y. U.S.A. LEAST PARTS



GERE GASOLINE ENGINES
SIMPLEST BOAT ENGINES MADE
CABIN—OPEN BOATS
ENGINE CASTINGS BOAT FRAMES
GEORGE YACHT LAUNCH WORKS
GRAND RAPIDS, MICHIGAN.
NEW CAT FOR 4 STAMPS



We Have an Inquiry for Your Goods

very often, and if we only knew your address, we could turn over to you inquiries by the hundred that come pouring into our office daily.

Read the "Business and Personal Want" Columns.

There you will find inquiries numbered. Read them carefully every week, and if you can furnish the goods required, write us at once, **GIVING THE NUMBER OF THE INQUIRY** every time, and we will put you in communication with the parties desiring the information. You may get an order or many orders by simply reading our **BUSINESS AND PERSONAL WANT COLUMNS** every week.

THE EDISON PHONOGRAPH

The Acme of Realism.



Perfect Reproductions of Sound are obtained by using EDISON RECORDS and GENUINE EDISON PHONOGRAPHS. Nine Styles. From \$10.00 to \$100.00. Catalogues everywhere. All dealers.

NONE GENUINE WITHOUT *Thomas A. Edison* TRADE MARK NATIONAL PHONOGRAPH CO., 135 Fifth Ave., New York

ONLY \$12.75 SEND NO MONEY



if you live within 500 miles of Chicago, (if further send \$1.00), cut out and return this ad. Mention No. 674, and we will send you this HAND-MADE ROLL TOP OAK DESK by freight, C. O. D. subject to examination. You can examine it at your nearest railroad station, and if found perfectly satisfactory and exactly as represented, the greatest value you ever saw or heard of, the equal of desks that others sell at almost double the price, then pay the railroad agent **\$12.75** and freight. OUR SPECIAL OFFER PRICE, **\$12.75** charges. The desk weighs about 180 pounds, and the freight for each 100 miles will be about 50 cents; 500 miles, about \$1.50. This desk is 4 ft. 2 in. long, 2 ft. 6 in. wide, 3 ft. 8 in. high. Made of carefully selected oak, beautifully finished in antique, full finished back, extension slides, quarter sawed sycamore pigeonhole case, combination lock on drawers, spring lock with duplicate keys on curtain, drawers on left side, lower partition for books, book closet on right hand side, drawers, pencil rest and card racks in interior, desk hand polished, dust proof curtain. THESE DESKS are made for under contract by one of the largest and best desk makers in this country. Every desk is put out under the manufacturer's BINDING GUARANTEE, and our special \$12.75 price barely covers the cost of material and labor, with but our one small percentage of profit added. Address, **SEARS, ROEBUCK & CO., CHICAGO, ILL.**

A COMPLETE Electrical Library

By PROF. T. O'CONOR SLOANE.

An inexpensive library of the best books on Electricity. Put up in a neat folding box, as shown in cut. For the student, the amateur, the workshop, the electrical engineer, schools and colleges. Comprising five books, as follows:

Arithmetic of Electricity 138 pages, . . . \$1.00
Electric Toy Making, 140 pages, . . . \$1.00

How to Become a Successful Electrician, 189 pages, . . . \$1.00
Standard Electrical Dictionary, 682 pages, \$3.00

Electricity Simplified, 158 pages, . . . \$1.00

Five volumes, 1,300 pages, and over 450 illustrations. A valuable and indispensable addition to every library. Our Great Special Offer.—We will send prepaid the above five volumes, handsomely bound in blue cloth, with silver lettering, and inclosed in a neat folding box, as shown in the illustration, at the Special Reduced Price of **\$5.00** for the complete set. The regular price of the five volumes is \$7.00.

MUNN & CO., Publishers,

361 Broadway, New York.

\$131,000,000 IN DIVIDENDS.

Equal, according to the last census, to practically \$10 for each family in the United States, was distributed by the mines and mining industries of our country during the past year (1900), and of those receiving these enormous dividends

Over 2,000 were Paid by Us

being stockholders in the several dividend-paying mines of which we are the sole fiscal agents, and which we have financed during the year, the

Highest Being 35% Lowest 12%

on the amount invested in the stocks, and a much larger ratio of profit on their cash market value at the present time should any one desire to sell.

Our Pamphlets of Working Mines, first issues and dividend payers, latest reports BOOKLET ABOUT OURSELVES, explaining in detail our successful plan of securing for our customers the large profits of legitimate mining investments with the risk of loss practically obviated, also COMBINATION ORDER BLANK which divides the investment among dividend payer and first issues, insuring large and regular income, will be of interest to investors desiring more than usual returns for surplus funds, mailed free with explanatory letter on request.

DOUGLAS, LACEY & CO.,

BANKERS AND BROKERS, 66 BROADWAY & 17 NEW ST., NEW YORK.

BRANCHES: CLEVELAND: The Cuyahoga Building, Boston: International Trust Bldg Philadelphia: The Betz Building, Chicago: The Fisher Building, St. Louis: The Security Building.

SIXTEENTH REVISED AND ENLARGED EDITION OF 1901.

The Scientific American Cyclopedia of Receipts, Notes and Queries.

15,000 RECEIPTS.

734 PAGES.

Price, \$5.00 in Cloth. \$6.00 in Sheep. \$6.50 in Half Morocco. Post Free.

This work has been revised and enlarged,

900 NEW FORMULAS.

The work is so arranged as to be of use not only to the specialist, but to the general reader. It should have a place in every home and workshop. A circular containing full TABLE OF CONTENTS will be sent on application.

Those who already have the Cyclopedia may obtain the

1901 APPENDIX.

Price, bound in cloth, \$1.00, postpaid.

MUNN & CO., Publishers, 361 BROADWAY, NEW YORK CITY.

**NEW YANKEE
DRILL GRINDER.**
Requires only ONE adjustment to grind any size drill within range of the machine.
SIMPLEST, FASTEST AND BEST.
Gage Jaws and Calipers done away with. Saves time, breakage and wear of Drills.
WILMARTH & MORMAN CO.,
153 Canal St., Grand Rapids, Mich., U.S.A.

Acetylene Gas Burners.
Schwarz Perfection Lava Burner.
Highest awards in all Acetylene Expositions. Made of one piece of lava. Are faultless and every one tested and guaranteed.
NO Blowing. Smoking. Carbonization. Perfect Alignment.
Sole Agents for the U. S. and Canada.
M. KIRCHBERGER & CO.,
50 Warren Street, New York.

PERFECT - PUMP - POWER.
is attained only in the TABER ROTARY PUMPS. They are mechanical, simple and durable. Will pump hot or cold fluid, thin or thick. Requires no skilled mechanic. Most power at least cost. All parts interchangeable. Made of iron, steel or bronze. Can be driven by belt, motor or engine attachment. Large Illustrated Catalogue free.
TABER PUMP CO., 32 Wells St., Buffalo, N.Y., U.S.A.

PERFORATED METALS
FOR ALL USES. MADE AS REQUIRED.
HARRINGTON & KING PERFORATING CO., CHICAGO.

YOU MAKE \$5.00 A DAY EASY
Gold, Silver, Nickel and Metal Plating.
At home or traveling, taking orders, using, selling Prof. Gray's Machines. Plates, Watches, Jewelry, Tableware, Bicycles, all metal goods. NO EXPERIENCE. Heavy plate. Modern methods. No toys. We do plating, make outfits, all sizes. Complete, all tools, lathes, materials, etc. Ready for work. The Royal, new dipping process, quick, easy. We teach you the art, furnish secrets, formulas, free. Write today. Pamphlet, samples, etc. FREE.
D. GRAY & CO., Plating Works, CINCINNATI, O.

NICKEL AND Electro-Plating
Apparatus and Material.
THE Hanson & Van Winkle CO.,
Newark, N. J.,
136 Liberty St., N. Y.,
30 & 32 S. Canal St. Chicago.

Gas Engine IGNITER
Complete with spark coil, \$12.00. The Best Thing on the market. Latest and most improved model.
Send for Circular.
The Carlisle & Finch Co., Sixth Street, Cincinnati, O.

DRIVING A PLEASURE
when holding your horse with an IMPERIAL BIT, giving 100 per cent more leverage than any other. Any lady can control the most vicious horse. Positive cure for tongue-jolting. Will prevent side pulling and driving on one line. Sent to any address, postpaid, upon receipt of price. In X.C. plate of imitation rubber, \$1. In fine nickel plate, \$2.
Imperial Bit and Snap Co., 14th Street, Ruelia, Wis.

**THE WILLIAMS
Pneumatic Pulley**
Double the grip of an ordinary pulley.
M. F. WILLIAMS & SONS,
ST. LOUIS, MO., U. S. A.

**MACHINES FOR ROLLING
SCREW
THREADS.**
Any size up to 1" diameter, 3" long. Four sizes of machines.
Send for Circulars.
BLAKE & JOHNSON,
P. O. Box 7, Waterbury, Conn.

BICYCLE TIRE REPAIRING.—THE
Mending of Single Tube Tires.—A practical article illustrating the method of inserting patches and plugs with pliers and pluggers, together with rubber band plugging and the use of puncture bands. 9 illustrations. Contained in SUPPLEMENT 1102. Price 10 cents. For sale by Munn & Co. and all newsdealers.

Williams' Shaving Stick

"The Only Kind that Won't Dry on the Face"



SOLD EVERYWHERE.

Williams' Shaving Stick, 25c.
Genuine Yankee Shaving Soap, 10c.
Luxury Shaving Tablet, 25c.
Swiss Violet Shaving Cream, 50c.
Williams' Shaving Soap (Barbers'), 6 Round Cakes, 1 lb., 40c. Exquisite also for toilet. Trial cake for 2c. stamp.

The only firm in the world making a specialty of SHAVING Soaps.

THE J. B. WILLIAMS CO., Glastonbury, Ct.
LONDON PARIS DRESDEN SYDNEY

The Pipe of the Century.

...THE... "MALLINCKRODT" PATENT
NICOTINE ABSORBENT AND VENTILATED SMOKING PIPE IS THE ONLY PIPE FIT FOR A GENTLEMAN'S USE.

You may appreciate the exquisite flavor and taste of a good smoking tobacco, but you can never have that enjoyment with a dirty, foul-smelling pipe thoroughly saturated with poisonous nicotine juices, so bitter and disgusting to the taste. This is effectually remedied in the "Mallinckrodt" where the juices are completely absorbed before reaching the mouth, and assuring a cool, clean and healthy smoke. Money refunded if not satisfactory. Prices from 30 to 50 cents each, according to size and finish. Over 100,000 sold in 1899 alone. Send for illustrated circular "S. A." with prices.

THE HARVEY & WATTS CO.,
387 Broadway, N. Y. Station E, Philadelphia.

Perfection Air Mattresses

FOR CAMP - YACHT - HOME - HOSPITAL.
NON-ABSORBENT, HYGIENIC, ODDLESS.
When deflated can be rolled into small package for storage or transportation.
Send for Illustrated Catalogue with Prices.
Mechanical Fabric Co. PROVIDENCE, R. I.

The Scientific American

PUBLICATIONS FOR 1901.

The prices of the different publications in the United States, Canada, and Mexico are as follows:

RATES BY MAIL.		
Scientific American (weekly), one year.		\$3.00
Scientific American Supplement (weekly), one year.		5.00
Export Edition of the Scientific American (monthly), in Spanish and English.		3.00
Building Edition of the Scientific American (monthly).		2.50

COMBINED RATES		
in the United States, Canada, and Mexico.		
Scientific American and Supplement.		7.00
Scientific American and Building Edition.		5.00
Scientific American, Scientific American Supplement, and Building Edition.		9.00

TERMS TO FOREIGN COUNTRIES.
The yearly subscription prices of Scientific American publications to foreign countries are as follows:

	U. S. Money.	English Money.
Scientific American (weekly),	\$4.00	0 16 5
Scientific American Supplement (weekly)	6.00	1 4 8
Building Edition of the Scientific American (monthly).	3.00	0 12 4
Export Edition of the Scientific American (monthly) in Spanish and English	3.00	0 12 4

COMBINED RATES TO FOREIGN COUNTRIES		
Scientific American and Supplement.	8.50	1 14 11
Scientific American and Building Edition.	6.50	1 6 9
Scientific American, Scientific American Supplement, and Building Edition.	11.00	2 5 2

The above rates include postage, which we pay. Remit by postal or express money order, or draft to order of MUNN & CO., 361 Broadway, New York.

HOW TO WRITE A BUSINESS LETTER.

Men who have mastered the art of Correspondence EARN LARGE SALARIES.
Our Book teaches the theory and practice the styles and forms of correct and successful business letter writing. Will improve your chances of success. Sent for on receipt of 25 cents.
CHAS. R. WIERS, Box 518, Trenton, N. J.

BRAINS AND CAPITAL SEEK A PARTNER.

I am a Designer and Modeler in Clay, Wax, Plaster, etc., and an expert Wood Carver, worker in Artistic Gold-plated, Brass, Spelter and Iron Goods, with all-around knowledge of the various industries. Practical factory experience in all different operations. Natural genius for invention and design. Had full charge of factory for several years. Possess small capital. Want to find a partner with capital, qualified to take the outside end, solicit orders, etc., to start in business in this country (any State) or in Cuba, Porto Rico or Mexico. Speak English and Spanish fluently, fair knowledge of French and Italian. 39 years old. Address J. S., P. O. Box 41, Byesville, Ohio, U. S. A.

WANTED Twelve good floor hands used to large work and six good planer hands. Write stating experience to P. O. BOX 1042, Philadelphia, Pa.

NEW 50 ft. Cabin Cruising Launch

For sale by owner. No use for it. Bargain! Write for photo, price, etc. W. J. Keith, Minneapolis, Minn.

What Do You Want To Buy?

We can tell you where to buy anything you want. Write us for the addresses of manufacturers in ANY line of business. Novelties, Special Tools, Machinery, Equipments, New Patent LABOR SAVING DEVICES. SEND FOR THE

Scientific American Manufacturers' Index

This Index is sent gratuitously to prospective purchasers, both in this country and abroad, who inquire for the addresses of dealers and manufacturers of the goods and machines classified therein. It is also sent to reliable Export Merchants in the United States and to the United States Consuls in all foreign countries. Address Inquiry Department.

MUNN & CO., Publishers of the SCIENTIFIC AMERICAN, 361 BROADWAY, NEW YORK.

**ELECTRICAL ENGINEERING
TAUGHT BY MAIL.**

Write for our Free Illustrated Book.
"CAN I BECOME AN ELECTRIC ENGINEER?"

We teach Electrical Engineering, Electric Lighting, Electric Railways, Mechanical Engineering, Steam Engineering, Mechanical Drawing, at your home by mail. Institute, Indorsed by Thos. A. Edison and others.
ELECTRICAL ENGINEER INSTITUTE.
Dept. A. 240-242 W. 28th St., New York.



Your scale of wages depends on your efficiency.

FREE SCHOLARSHIP

The Trustees of the American School of Correspondence will award a limited number of Free Scholarships in Mechanical, Electrical, Marine, Stationary, and Locomotive Engineering, including a complete course in Mechanical Drawing. Application blank on request.

American School of Correspondence, Boston, Mass.
(Incorporated in the Commonwealth of Massachusetts) Mention this paper.

HOW TO MAKE AN ELECTRICAL FURNACE for Amateur's Use.—The utilization of 110 volt electric circuits for small furnace work. By N. Monroe Hopkins. The valuable article is accompanied by detailed working drawings on a large scale, and the furnace can be made by any amateur who is versed in the use of tools. This article is contained in **SCIENTIFIC AMERICAN SUPPLEMENT, No. 1182.** Price 10 cents. For sale by MUNN & CO., 361 Broadway, New York City, or by any bookseller or newsdealer.

THE LOZIER GAS ENGINE

ALWAYS READY.

No tinkering and fussing. Just a turn of the wheel and she works. A chain is as strong as its weakest link. An engine is as perfect as its poorest part. If your engine has a poor oiler, a defective spark, an inferior mixer or any other cheap parts, your boat is useless. There is nothing made that in any sense competes with the Lozier Marine Gas Engine. It is the only perfected contrivance of its kind. Learn about this.

Our 1901 advance catalogue which we will send you upon receipt of five cents in stamps, will post you on boat power and save you endless trouble next summer.

THE LOZIER MOTOR CO.,
26 Water Street, Plattsburgh, N. Y.

PSYCHRATISM

The New Discovery of the Age.

THE VERNON ACADEMY

will tell you all about it

FREE OF CHARGE

The new discovery of Prof. Albert Vernon, the marvel of the Century. A thousandfold more powerful than **HYPNOTISM**. A knowledge of the wonderful resources of this science will unfold to you the secrets of success and make clear and plain all that has seemed so mysterious and that has been attributed to supernatural agency or hypnotism during past ages. You may have a wonderful, comprehensive 100-page book by this gifted man by sending your name to us at once. **Write today. It is absolutely FREE.** Address **VERNON ACADEMY OF MENTAL SCIENCES,** 2203 East Avenue, Rochester, N. Y.

BALL BEARING AXLES AND RUBBER TIRES.—A paper read before the Carriage Builders' National Convention, Philadelphia, October, 1894, showing the advantage to be derived from the use of ball bearings and pneumatic tires in road vehicles. Contained in **SCIENTIFIC AMERICAN SUPPLEMENT, No. 992.** Price 10 cents. To be had at this office and from all newsdealers.

PERSONAL MAGNETISM

It triumphs over obstacles; it enables you to gratify your highest ambitions; to achieve; to accomplish; to win. It marks the difference between success and failure and makes man the supreme master of his destiny. By our new system you can learn this wonderful science in a few days at your own home, you can cure diseases, bad habits and wield wonderful power and influence over others. Our richly illustrated book on **HYPNOTISM, PERSONAL MAGNETISM, MAGNETIC HEALING, etc.** tells how. **It's free.** It is intensely interesting and full of startling surprises. It has been the means of starting thousands of persons on the road to success. A postal card dropped in the box at the corner will bring this wonderful book to your very door. Address, **New York Institute of Science,** Dept. P. T. 9, Rochester, N. Y.

Building Edition

Scientific American

MONTHLY, \$2.50 PER ANNUM; SINGLE NUMBERS, 25 CENTS.

The BUILDING EDITION for 1901 is the handsomest magazine in the United States. It has many new and important features. Send 25 cents for the March number, and see the new departments. The illustrations and cover are more attractive than ever. Send for "Are You About to Build," and be convinced.

NEW DEPARTMENTS.

Monthly Comment.

Interviews with Architects.

New Books.

New Building Patents.

Notes and Queries.

Digest of Current Articles.

MUNN & CO., Publishers, 361 Broadway, NEW YORK.

SALESMEN AND AGENTS WANTED

BIG WAGES.—Our Famous Puritan Water Still, a wonderful invention—not a filter, 25,000 already sold. Demand enormous. Everybody buys. Over the kitchen stove it furnishes plenty of distilled, aerated drinking water, pure, delicious and safe. Only method. Distilled Water cures Dyspepsia, Stomach, Bowel, Kidney, Bladder and Heart Troubles; prevents fevers and sickness. Write for Booklet. New Plan, Terms, etc. **FREE** **Harrison Mfg. Co.,** 297 Harrison Bldg., Cincinnati, O.

PATENTS

Anyone sending a sketch and description may quickly ascertain our opinion free whether an invention is probably patentable. Communications strictly confidential. Handbook on Patents sent free. Oldest agency for securing patents. Patents taken through Munn & Co. receive special notice, without charge, in the

Scientific American.

A handsomely illustrated weekly. Largest circulation of any scientific journal. Terms, \$3 a year; four months, \$1. Sold by all newsdealers.

MUNN & Co. 361 Broadway, New York
Branch Office, 625 F St., Washington, D. C.

DYKES AUTO TOOL SET No. 10.

BUILD YOUR OWN AUTOMOBILE.

Send for new Cat. Supplement.

ST. LOUIS AUTOMOBILE AND SUPPLY CO.,
2222 St. Charles St., St. Louis, Mo.
First Auto. Supply Co. in America.

The AUTOSPARKER

The completion of the Gas Engine.

Throw away your batteries and use them no more. The Autosparker saves its cost many times over during the life of your engine. Address **MOTSINGER DEVICE MFG CO.,** Pendleton, Ind., U. S. A. or any gas engine or motor carriage manufacturer.

If Your Eye Could See

the filth that passes through ordinary water faucets you would be alarmed and disgusted. These germs are the cause of most diseases. Pure water would prevent them and perfectly pure water can be produced only by using the widely celebrated

Berkefeld Filter,

which is constructed on the most scientific and hygienic principle. Easy to clean and care for. Rapid filtration. One gallon of pure water in 4 minutes.

Berkefeld Filter Co., 2 Cedar St., New York.

\$5.85

17 JEWEL

adjusted, patent regulator, stem wind and stem set, genuine

NATIONAL SPECIAL

newest, latest, of Gents' size. **WARRANTED 20 YEARS.** 14K Gold plate hunting case, elegantly engraved. Fit for a king. No better watch made. Must be seen to be appreciated. Special offer for next 90 days, send your full name and address and we will send this watch C.O.D. with privilege to examine. If found satisfactory pay agent \$5.85 & express charges. A guarantee and beautiful chain & charm sent free with every watch. Write at once as this may not appear again. **NAT'L MFG. & IMPORTING CO.,** 334 Dearborn St., B 420, Chicago, Ill.

\$19.30 DESK

50 in. long. 80 in. wide.

quarter sawed oak front, oak throughout, letter files, blank drawers, document file, pigeon hole boxes, extension slides, letter holders and drops. Large, complete, attractive and convenient.

DESKS \$10 and up.

Can furnish your Office or Home throughout at **FACTORY PRICES.** Catalog No. 153, Office Furniture.

E. H. STAFFORD & BRO., Steinway Hall, Chicago.

DICKERMAN'S DURABLE DESKS

Don't buy until you get our catalogue—100 pages of money saving values.

AMERICAN STORE STOOL CO., 33 Howard St., New York

After Eighteen Years

this invention is used in every country in the world "GLACIER" is a substitute for Stained Glass. Looks as well and costs much less. For the home as well as the church. Samples sent to interested parties. Made by McCaw, Stevenson & Orr, Ltd., Belfast, Ireland. Address letters to **G. QUAIL, U. S. Agent, 336 Broadway, New York.**

PROSPECTIVE BOAT BUYERS

By constructing your boat from a set of my **Boat Building Materials** more than one-half the boat factory's price can be realized. Also economize freight 500 per cent. Launches, Sail and Row-boats, Gasoline Engines.

FRED MEDART, 3545 DeKalb Street, St. Louis, Mo.

GASOLINE MOTOR CASTINGS

For MARINE, VEHICLE and BICYCLE MOTORS, with Working Drawings.

LOWELL MODEL CO., 22 Wiggin St., Lowell, Mass.

Telephones,

for Interior, Short Line, Intercommunicating and Hotel Work. Write us for prices, catalog, etc., with testimonials and references. Estimates cheerfully furnished. Agents wanted.

THE SIMPLEX INTERIOR TELEPHONE CO., 431 Main St., Cincinnati, Ohio.

MORAN FLEXIBLE JOINT

for Steam, Air or Liquids.

Made in all sizes to stand any desired pressure.

Moran Flexible Steam Joint Co., Inc'd, 147 Third Street, LOUISVILLE, KY.

For the Celebrated **Smith Improved Automatic FIBRE CLEANING MACHINE.** Best of its kind in existence.

AGRICULTURAL IMPLEMENTS AND SPECIAL MACHINERY.

APPLY TO **THE SPANGLER MFG. CO., YORK, PA**

REVERSING STEAM TURBINE.—PARSON'S recently perfected turbine for boats. Illustrations showing details. Contained in **SCIENTIFIC AMERICAN SUPPLEMENT, No. 1158.** Price 10 cents, by mail, from this office, and from all newsdealers.

ARTESIAN

Wells, Oil and Gas Wells drilled by contract to any depth from 50 to 300 feet. We also manufacture and furnish everything required to drill and complete same. Portable Horse Power and Mounted Steam Drilling Machines for 100 to 1200 feet. Write us stating exactly what is required and send for illustrated catalogue. Address **PIERCE WELL ENGINEERING AND SUPPLY CO.,** 136 LIBERTY STREET, NEW YORK, U. S. A.

WANTED.—ELECTRICIAN AND THREE Draftsmen. An examination of applicant will be held at the Navy Yard, New York, February 26, 1901, for electrician at \$1,200 per annum, one second-class electrical draftsman at \$4.00 per diem, one third-class electrical draftsman at \$3.25 per diem and one fourth-class electrical draftsman at \$3.00 per diem. The examination will be open to all comers who can give evidence of experience in the kind of work for which they seek employment, and who are citizens of the United States. Applications will be addressed to the Commandant, Navy Yard, New York, and must be delivered to him on or before Monday, February 25. No application received after that date will be considered. Each applicant will state in his application his name, age, residence, citizenship, present occupation and previous employment or work done. The applications will be accompanied by evidence of citizenship, and by certificates, preferably from previous employers, as to character, habits of industry and sobriety and skill and experience in work of the kind required.

JOHN D. LONG, Secretary of the Navy.

WANTED.—DRAFTSMEN, AN EXAMINATION of applicants will be held at the Navy Yard, Boston, Mass., February 26, 1901, for one first-class mechanical draftsman at \$5.04 per diem, Boston Yard, and two assistant ship draftsmen at \$4.00 per diem. Office of Superintendent Naval Constructor, Bath, Me. The examination will be open to all comers who can give evidence of experience in the kind of work for which they seek employment, and who are citizens of the United States. Applications will be addressed to the Commandant, Navy Yard, Boston, Mass., and must be delivered to him on or before Monday, February 25. No application received after that date will be considered. Each applicant will state in his application his name, age, residence, citizenship, present occupation, and previous employment or work done. The applications will be accompanied by evidence of citizenship, and by certificates, preferably from previous employers, as to character, habits of industry and sobriety, and skill and experience in work of the kind required.

JOHN D. LONG, Secretary of the Navy.

ICE MACHINES, Corliss Engines, Brewers' and Bottlers' Machinery. THE VILTER MFG. CO., 839 Clinton Street, Milwaukee, Wis.

MODELS & CEARSE CATALOGUE FREE. 193 CLARK CHICAGO.

NEW YORK SHOPPING by a responsible and experienced lady. Send for circular. **MRS. LORD, 53 West 24th Street, New York City.**

MODELS & EXPERIMENTAL WORK. Inventions developed. Special Machinery. **E. V. BAILLARD, Fox Bldg., Franklin Square, New York.**

WANTED To purchase or manufacture on a royalty, patent in machine tools of new design, or now on the market, for which there is a legitimate demand at a fair profit. Address **Lock Box 21, Station B, Cleveland, Ohio.**

STEEL TYPEWRITER TYPE TYPE WHEELS, MODELS & EXPERIMENTAL WORK, SMALL MACHINERY NOVELTIES, ETC. **NEW YORK STENCIL WORKS 100 NASSAU ST. N. Y.**

1/2 H. P. GAS ENGINE CASTINGS Materials and Blue Prints. Write for Catalogue 9. **PARSELL & WOOD, 124-131 W. 31st Street, New York.**

FOR SALE.—Patent No. 250,236. Sulkey Rakes. A decided success. New, handy, can be applied to any rake. For terms apply to **E. E. FOREMAN, Durango, Colorado.**

American Gardening 10 Sample Copies, separate issues, 10 cents. Published at 136 Liberty St., New York.

MECHANICAL PATENT (new) on detachable **HORSE SHOE CALK.** Fits any shoe. Big seller. **FOR SALE CALK CO., 101 West Av. Buffalo, N. Y.**

FACTORY FOR SALE.—Three-story, brick, 25x100, with iron extensions; complete equipment metal working machinery; near Trunk line; rare chance. **S. DANIELS, 163 Washington Street, New York.**

D'AMOUR & LITTELDAL MACHINE CO. 130 WORTH ST. NEW YORK. **PATTERN AND MODEL MAKERS.**

HOW TO MAKE A DYNAMO with full working drawings. Price 10 cents. Castings for the same, \$3.75, with directions for building. "How to Make a Storage Battery." Price 10 cents.

326 FIRST PREMIUMS SEND FOR FREE CATALOGUE. **Prairie State Incubator Co., Homer City, Pa.**

EVERY BICYCLE RIDER, DEALER & REPAIRER should write us for full information concerning our **SPECIALTY.** Indispensable wherever introduced. Increases business and profits. Certain demand. **THE AVERY & JENNESS CO.,** 30 W. Washington St., Chicago, Ill.

\$3 a Day Sure Send us your address and we will show you how to make \$3 a day absolutely sure; we furnish the work and teach you free, you work in the locality where you live. Send your address and we will explain the business fully, remember we guarantee a clear profit of \$3 for every day's work, absolutely sure. Write at once. **ROYAL MANUFACTURING CO., Box 354, Detroit, Mich.**

Brass Band

Instruments, Drums, Uniforms, & Supplies. Write for catalog, 445 illustrations, FREE; it gives information for musicians and new bands. **LYON & HEALY,** 88 Adams St., CHICAGO.

ELECTRIC AUTOMOBILE.—DIRECTIONS, with many illustrations, for making a complete machine from two bicycles are given in **SUPPLEMENT No. 1195.** The motor and battery are also treated of in detail. Price 10 cents. For sale by Munn & Co. and all newsdealers.

D. L. HOLDEN 14 SOUTH BROAD ST. PHILADELPHIA PA. **SOLE MANUFACTURER** **REGELED ICE MACHINES** SEE FIRST PAGE SCIENTIFIC AMERICAN SEPT. 2, 1899.

DO HENS PAY? A question and a hundred more are carefully covered by a study of our **20th CENTURY POULTRY BOOK.** It handles the entire poultry subject in a masterful and practical way. The famous **RELIABLE INCUBATORS AND BROODERS** used all over the U. S. and in 51 foreign countries receive attention. Book mailed for 10c. **RELIABLE INCUBATOR AND BROODER CO., Box B 1st Quincy, Ill.**

LIFE PRODUCERS **SUCCESSFUL INCUBATORS, LIFE PRESERVERS, SUCCESSFUL BROODERS.** All about them in our 154 page catalogue, mailed for 6 cents in stamps. **DES MOINES INCUBATOR CO., Box 75 Des Moines, Ia.**

FOR MEN OF BRAINS Cortez CIGARS —MADE AT KEY WEST—

These Cigars are manufactured under the most favorable climatic conditions and from the mildest blends of Havana tobacco. If we had to pay the imported cigar tax our brands would cost double the money. Send for booklet and particulars.

CORTEZ CIGAR CO., KEY WEST.

THOROUGH INSPECTIONS


AND INSURANCE AGAINST LOSS OR DAMAGE TO PROPERTY AND LOSS OF LIFE AND INJURY TO PERSONS CAUSED BY

STEAM-BOILER EXPLOSIONS

J. M. ALLEN, PRESIDENT W. B. FRANKLIN, VICE PRESIDENT
J. B. PIERCE, SECRETARY F. B. ALLEN, 2ND VICE PRESIDENT
L. B. BRAINERD, TREAS. L. F. MIDDLEBROOK, ASST. SECY.

The Rule of the Road


At the present day is to be better equipped for travel than is possible with horse-drawn vehicle. A



WINTON MOTOR CARRIAGE is suitable for all weathers, is speedy, sure, safe, strong, simple, economical and at all times reliable. Ride 150 miles without leaving the seat. Catalogue illustrating and describing new models will interest you.

THE WINTON MOTOR CARRIAGE CO., 486 Belden Street, Cleveland, Ohio, U. S. A.
EASTERN DEPOT, 150-152 East 58th Street, New York.

Handsome, Durable Practical



We are the Pioneer Automobile Manufacturers of America, and have passed the experimental stage. Profit by our experience—don't be misled. The gasoline system machines hold all the long distance records, both in America and Europe. Buy a gasoline carriage and buy the best, the new improved HAYNES-APPERSON.

New Catalogue now ready describing our gasoline system, and one, two and three seated carriages.

THE HAYNES-APPERSON CO., Kokomo, Indiana, U. S. A.


CHARTER ENGINE USED ANY PLACE BY ANY ONE FOR ANY PURPOSE

FUEL—Gasoline, Gas, Distillate
Stationaries, Portables, Engines and Pumps, Hoisters

State Your Power Needs

CHARTER GAS ENGINE CO., Box 148, STERLING, ILL.

GARDNER'S STOCK
C. H. BISHOP & CO. 1012 N. CANAL ST. CHICAGO ILL. U. S. A.



BRISTOL'S RECORDING INSTRUMENTS.


Pressure Gauges, Vacuum Gauges, Voltmeters, Amperemeters, Wattmeters, and thermometers, make continuous records Day and Night. Will pay for themselves. Every instrument fully guaranteed and sent on 30 days' trial. Send for Circulars and Specimen Chart.

The Bristol Company Waterbury, Conn.

Scales All varieties at lowest prices. Best Railroad Track and Wagon or Stock Scales made. Also 1000 useful articles, including Saws, Sewing Machines, Bicycles, Tools, etc. Save Money. Lists Free. CHICAGO SCALE CO., Chicago, Ill.



Carbide Feed ACETYLENE GENERATORS



are endorsed by the U. S. Government, by the State of Pennsylvania, and by all other disinterested authorities.

They embody the latest and most approved principles of construction, and are guaranteed by the largest concern engaged in the business to be of perfect workmanship.

Made from the best material by expert mechanics.

ECONOMICAL AND SAFE. EASY OF OPERATION.

J. B. COLT CO., Dept. S.
108 Fulton Street, New York.
146 Franklin Street, Boston.
189 La Salle Street, Chicago.
421 Chestnut Street, Philadelphia.


WALTHAM WATCHES

The best and most reliable timekeepers made in this country or in any other.

"The Perfected American Watch", an illustrated book of interesting information about watches, will be sent free upon request.

American Waltham Watch Company,
Waltham, Mass.

FOR MEN JAMES MEANS' \$2.50 SHOE



KNOWN AND APPROVED BY THE PUBLIC FOR 23 YEARS.

SOLD BY LEADING RETAILERS.

Made in a variety of styles and leathers. Sewed. Smooth innersoles.


Distributed at wholesale by

MORSE & ROGERS OF NEW YORK.

View of Pipe Open and Closed.



The Open Pipe TWO HALVES MAKE A WHOLE 50c.



The only clean pipe on earth. Always sweet, pure and clean, free from poisonous nicotine. A pipe that opens in the center, so that every part can be thoroughly cleaned. The bowl is made in two sections, which are united together with an interior screw lock. When the pipe is closed it is absolutely airtight, and looks like the ordinary briar, but by twisting the bowl the interior is exposed exactly as shown in the cut. The only pipe in the world that never smells, never bites, never tastes bad. Made of the finest genuine briar, with curved or straight stem, beautifully finished.

Send us fifty cents in 2c. stamps or money order, for a sample. If it is not just what you want and more than satisfactory, your money back without a word. Agents wanted at once. BUFFALO BRIAR PIPE CO., 448 Washington Street, Buffalo, N. Y.

ON A NEW PRINCIPLE our MUFFLER does the work. If your exhaust makes a racket, write Pat. applied for. us, and we will tell you how to cure it. Automobile, Marine and Stationary Mufflers. LOOMIS AUTOMOBILE CO., Westfield, Mass.

JESSOP'S STEEL THE VERY BEST FOR TOOLS, SAWS, ETC.

WM. JESSOP & SONS Ld 91 JOHN ST. NEW YORK

A SMALL CAPITAL brings good returns if invested in a MAGIC LANTERN or Stereopticon for exhibition purposes. Write for 280 page illustrated catalogue free. McALLISTER, Mfg. Optician, 49 Nassau St., N. Y.

SHOE BLACKING—FORMULAS FOR liquid and solid blacking are given in SUPPLEMENT Nos. 1213 and 1239. Price 10 cents each. For sale by Munn & Co. and all newsdealers.

ASBESTOS FIRE-VELT COVERINGS
PURE ASBESTOS ABSOLUTELY FIRE PROOF
REFRIGERATE WITH AIR CELLS PERFECT NON-CONDUCTORS
STRONG, LIGHT, FLEXIBLE, EASILY APPLIED
MADE IN SECTIONS THREE FEET LONG
FIT STANDARD PIPE 1/2 INCH TO 16 INCHES.
H. W. JOHNS MFG CO.
NEW YORK, CHICAGO, PHILADELPHIA, BOSTON
ASBESTOS MATERIALS. LIQUID PAINTS & STAINS
ROOFING MATERIALS. ELECTRICAL MATERIALS.

The New England Watch Co. ARTISTIC SPECIALTIES

for the Season are shown
In Our Blue Book for Ladies'
In Our Red Book for Men's
Watches.

Either or both sent on application.

37 Maiden Lane, 149 State Street,
New York, N. Y. Chicago, Ill.
Spreckels Building, San Francisco, Cal.

Cracks in Floors

are unsightly, unclean and unsanitary. GRIPPIN'S WOOD, CRACK AND CREVICE FILLER is the only perfect remedy. A Paste, easily applied and is elastic, adhesive and non-sinkable. Send \$1.00 for enough to treat an ordinary room of 200 sq. ft. One lb. covers 40 sq. ft. Price 25 cts. per lb. Manufactured only by the GRIPPIN MFG. CO., Lock Box L, NEWARK, NEW YORK (Send stamp for booklet.)



A Line to Workers who are Drifting

Send for a free copy of circular:

Salaried Positions for Learners

It shows what wonderful things have been done and are being done in preparing young men and women to earn good salaries in positions that require special knowledge. It tells how you can obtain a salaried position in your chosen profession, trade or business, and support yourself while learning how to earn more. You can become a

Mechanical Engineer Electrician Architect

250,000 students and graduates in Mechanical, Electrical, Steam, Civil and Mining Engineering; Architecture; Drawing and Designing; Lettering; Chemistry; Telegraphy; Telephony; Teaching; Stenography; Book-keeping; English Branches. When writing, state subject in which interested.

INTERNATIONAL CORRESPONDENCE SCHOOLS,
Established 1891. Capital, \$1,500,000.
Box 942 SCRANTON, PA.


WATERPROOF GLUE

A NEW GLUE which is strictly WATER-PROOF. Information and prices supplied by the

CASEIN COMPANY OF AMERICA,
74 JOHN ST., NEW YORK, N. Y.

ACETYLENE

DO YOU KNOW that the most light, least trouble, greatest comfort can be secured by using good burners. The best burner is D. M. STEWARD'S WONDER. Write, inclosing 25 cents, for sample. STATE LINE TALC CO., Chattanooga, Tenn., U. S. A.



(VIEW OF TRAIN BEARING FOURTEEN GRIFFIN MILLS TO IOLA CEMENT CO.)

"Most Satisfactory and Economical."

IOLA PORTLAND CEMENT COMPANY.

BRADLEY PULVERIZER CO., Boston, Mass.

DETROIT, MICH., Oct. 16, 1900.

Gentlemen:—Your inquiry as to the satisfaction the Griffin Mills are giving us duly received. We have forty-two 30 in. Griffin Mills in our plant. The writer has had a large experience with most kinds of grinding machinery, and is prepared to say that for grinding Portland cement clinker the Griffin Mill is the most satisfactory and economical grinding machine on the market. Each of the above mills has at times run over ten barrels per hour, and on long runs has averaged nine and a half barrels each per hour.

Yours truly,

IOLA PORTLAND CEMENT CO.

(Sgd.) Per JOHN T. HOLMES, Managing Director.

We invite everyone interested in reducing refractory substances to an even degree of fineness to write for descriptive catalogue of this remarkable mill. It will surely interest you and may save you money.

THE BRADLEY PULVERIZER CO., BOSTON.